

Alamo Colleges WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203

ISSUE FOR CONSTRUCTION

2024/06/14



BOARD OF TRUSTEES

JOE ALDERETE JR.
GLORIA RAY
ANNA URIEGAS BUSTAMANTE
DR. LORENA PULIDO
ROBERTO ZÁRATE
DR. GENE SPRAGUE
DR. YVONNE KATZ
CLINT KINGSBERY
LESLIE SACHANOWICZ
BRANDON AVIADO

DISTRICT 1
ASSISTANT SECRETARY, DISTRICT 2
DISTRICT 3
SECRETARY, DISTRICT 4
DISTRICT 5
DISTRICT 6
DISTRICT 7
VICE CHAIR, DISTRICT 8
DISTRICT 9
STUDENT TRUSTEE

ADMINISTRATION

DR. ADENA WILLIAMS LOSTON
RANDALL DAWSON
WESLEY B. WELLS
GEORGE H. JOHNSON, III
CHRISTOPHER METSGAR
DR. KIMBERLEY IRVING-CONAWAY
DR. DIANE GAVIN
MARSHA P. HALL

PRESIDENT
VICE-PRESIDENT FOR ACADEMIC SUCCESS
VICE-PRESIDENT FOR STUDENT SUCCESS
INTERIM VICE-PRESIDENT FOR COLLEGE
DEAN FOR ACADEMIC SUCCESS, HEALTH SCIENCES
DEADN FOR ACADEMIC SUCCESS, ACADEMIC SERVICES
DEAN OF PERFORMANCE EXCELLENCE
DIRECTOR OF STRATEGIC INITIATIVES

ARCHITECT
PBK ARCHITECTS, INC
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

ASSOCIATE ARCHITECT
B&A ARCHITECTS
222 Ridgcrest Dr
San Antonio, TX 78209
T 210-829-1898

CIVIL ENGINEER
GESSNER
401 W. 26th St, Ste 3
Bryan, TX 77803
T 979-680-8840

STRUCTURAL ENGINEER
LUNDY & FRANKE ENGINEERING
549 Heimer
San Antonio, TX 78232
T 210-979-7900

LANDSCAPE ARCHITECT
EDGELAND GROUP
11 Greenway Plaza, 15th Floor
Houston, TX 77046
T 713-460-0988

MEP ENGINEER
LEAF
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

THEATER CONSULTANT
WJHW
12175 Network Blvd., Suite 150
San Antonio, TX, 78249
T 210-561-9800

ENVELOPE CONSULTANT
BEAM PROFESSIONALS
601N.W.LOOP 410, Suite 400
San Antonio, TX 78216
T 210-829-0123

WFAC Black Box Addition PKG 1

1801 Martin Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION

Table with 3 columns: SHEET NUMBER, SHEET NAME, and content listing architectural, mechanical, and electrical details.

ADD ALTERNATES

- 1. PROVIDE SEPARATE PRICING TO REMOVE THE LOBBY ADDITION IN FRONT OF THE EXISTING WATSON THEATER ENTRANCE. THIS IS TO INCLUDE PIERS, FOUNDATION.
2. MUD SLAB:
2A - PROVIDE SEPARATE PRICING TO REMOVE MUD SLAB DOWN TO A PATHWAYS FROM THE FLOOR HATCH TO THE PLUMBING DRAINS. REFER TO SHEET A-100.
2B - PROVIDE SEPARATE PRICING TO REMOVE THE MUD SLAB.

ABBREVIATIONS AND LEGEND KEYS

Table of abbreviations and legend keys including symbols for structural, mechanical, electrical, and plumbing elements.


GENERAL NOTES

- A. THE CONTRACT DOCUMENTS ARE TO INCLUDE AIA DOCUMENT A201 'GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION'. CLIENT SHALL BE DESIGNATED AS 'THE OWNER'. PBK ARCHITECTS, INC. SHALL BE DESIGNATED AS 'THE ARCHITECT'. FACILITY SHALL BE DESIGNATED AS 'THE LANDLORD'. THE CONTRACT DOCUMENT SHALL ALSO INCLUDE THE AGREEMENT, PERFORMANCE AND PAYMENT BONDS, GENERAL CONDITIONS, SUPPLEMENTARY CONDITIONS, THE SPECIFICATIONS, CONTRACT DRAWINGS ADDENDA, AND CONTRACT MODIFICATIONS, BUILDING RULES AND REGULATIONS & ANY OTHER DOCUMENTS REQUIRED BY THE OWNER.
B. THE WORK SHALL BE DONE IN ACCORDANCE WITH THE RULES AND REGULATIONS OF ALL APPLICABLE SAFETY AND BUILDING CODES, AND AS APPROVED BY THE AUTHORITY HAVING JURISDICTION. CONTRACTOR IS RESPONSIBLE FOR SECURING AND PAYING FOR ALL PERMITS REQUIRED FOR THE WORK AND FOR THE SCHEDULING OF ALL REQUIRED INSPECTIONS DURING THE COURSE OF THE WORK.
C. CONTRACTOR SHALL REVIEW AND VERIFY EXISTING CONDITIONS AS PROVIDED IN THE CONSTRUCTION DOCUMENTS. CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ALL DISCREPANCIES, ERRORS, INCONSISTENCIES OR AMBIGUITIES PRIOR TO PROCEEDING WITH THE WORK.
D. CONTRACTOR SHALL BE RESPONSIBLE FOR, AND PROVIDE PROTECTION OF, ANY EXISTING FINISHES, MATERIALS, AND EQUIPMENT TO REMAIN. CONTRACTOR SHALL REPAIR OR REPLACE ANY DAMAGED FINISHES, MATERIALS, AND EQUIPMENT AS A RESULT OF THE WORK. ALL EXISTING FINISHES TO REMAIN SHALL BE CLEANED AT THE COMPLETION OF CONSTRUCTION. CONTRACTOR SHALL PHOTOGRAPH AND DOCUMENT ALL EXISTING DAMAGES, AND PROVIDE TO THE ARCHITECT, PRIOR TO PROCEEDING WITH THE WORK.
E. ALL MATERIALS AND SYSTEMS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. ALL CONSTRUCTION SHALL BE OF INDUSTRY STANDARD OR BETTER. THE ARCHITECT SHALL BE FINAL JUDGE OF QUALITY.
F. ONLY NEW MATERIALS AND EQUIPMENT OF RECENT MANUFACTURE, OF STANDARD QUALITY, AND FREE FROM DEFECTS, WILL BE PERMITTED IN THE WORK, UNLESS OTHERWISE NOTED. REJECTED MATERIALS AND EQUIPMENT SHALL BE REMOVED IMMEDIATELY FROM THE WORK AND REPAIRED WITH MATERIALS AND EQUIPMENT OF THE QUALITY SPECIFIED. FAILURE TO REMOVE REJECTED MATERIALS AND EQUIPMENT SHALL NOT RELIEVE CONTRACTOR FROM THE RESPONSIBILITY FOR QUALITY OF MATERIAL AND EQUIPMENT USED NOR FROM ANY OTHER OBLIGATION IMPOSED BY THE CONTRACT.
G. DO NOT SCALE DRAWINGS. STATED & WRITTEN DIMENSIONS GOVERN. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD AND SHALL BE RESPONSIBLE FOR THEIR ACCURACY. NO EXTRA CHARGE OR COMPENSATION SHALL BE ALLOWED BECAUSE OF DIFFERENCE BETWEEN ACTUAL DIMENSIONS AND THOSE INDICATED ON THE DRAWINGS, UNLESS THEY CONTRIBUTE TO A CHANGE IN THE SCOPE OF THE WORK. ANY DIFFERENCE FOUND SHALL BE SUBMITTED TO THE ARCHITECT FOR COORDINATION PRIOR TO ORDERING, MANUFACTURING, OR PROCEEDING WITH THE WORK. HORIZONTAL DIMENSIONS INDICATED ARE TO/FROM FACE OF FINISH, UNLESS NOTED OTHERWISE. VERTICAL DIMENSIONS ARE FROM TOP OF FLOOR SLAB EXCEPT WHERE NOTED TO BE ABOVE FINISHED FLOOR (AFF). DIMENSIONS ARE NOT ADJUSTED WITHOUT APPROVAL OF ARCHITECT UNLESS NOTED OTHERWISE.
H. CONTRACTOR SHALL VERIFY THAT NO CONFLICTS EXIST BETWEEN THE LOCATIONS OF EXISTING AND PROPOSED NEW MECHANICAL, ELECTRICAL, PLUMBING, DATA, AND SPRINKLER EQUIPMENT (INCLUDING BUT NOT LIMITED TO STRUCTURAL MEMBERS, PIPING, DUCT WORK, CONDUIT AND SPRINKLERS) AND THAT CLEARANCES FOR INSTALLATION AND MAINTENANCE OF EQUIPMENT ARE PROVIDED. ELEMENTS IN CONFLICT SHALL BE DOCUMENTED AND PROVIDED TO THE ARCHITECT PRIOR TO PROCEEDING WITH THE WORK.
I. CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH SHOP DRAWINGS FOR REVIEW AND APPROVAL FOR ALL, BUT NOT LIMITED TO, THE FOLLOWING: SHOP-FABRICATED MILLWORK, CARPET LAYOUT, FLOORING, LIGHT FIXTURES, DOORS, MISC. STEEL, METAL FABRICATION, GLASS/GLAZING, SPRINKLER LAYOUTS, HARDWARE. SHOP DRAWINGS SHALL BE SUBMITTED IN THE FORM OF 3 SETS OF PRINTS. SHOP DRAWINGS SHALL NOT BE REPRODUCTIONS OF CONTRACT DOCUMENTS. MATERIAL SUBMITTALS (S/SAMPLES) SHALL BE PROVIDED FOR WOOD, FASTENERS, ACRYLIC, CARPET, TILE, BASE, PAINT, LAMINATE AND ANY OTHER MATERIALS INDICATED IN THE SHOP DRAWINGS.
J. CONTRACTOR SHALL PROVIDE THE ARCHITECT WITH MANUFACTURER'S CUT SHEETS AND SPECIFICATIONS FOR ALL EQUIPMENT INCLUDING BUT NOT LIMITED TO LIGHT FIXTURES, PLUMBING EQUIPMENT, ELECTRICAL EQUIPMENT, FANS, SUPPLEMENTARY HEATING AND COOLING ELEMENTS, ALL HARDWARE AND SECURITY EQUIPMENT.
K. CONTRACTOR SHALL NOT PROCEED WITH WORK FOR WHICH ADDITIONAL COMPENSATION BEYOND THE CONTRACT AMOUNT IS EXPECTED WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT AND OWNER. FAILURE TO OBTAIN SUCH AUTHORIZATION SHALL INVALIDATE A CLAIM FOR EXTRA COMPENSATION. CONTRACTOR SHALL NOT PROCEED WITH WORK WHICH, IF COMPLETED IN STRICT CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS, WILL RESULT IN ADDITIONAL WORK BEYOND THE SCOPE OF THE CONTRACT WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT AND OWNER. ANY FIELD CONDITIONS THAT SIGNIFICANTLY VARY FROM THE CONTRACT DOCUMENTS OR WILL RESULT IN ADDITIONAL WORK, SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO PROCEEDING WITH WORK.
L. CONTRACTOR SHALL REVIEW AND COORDINATE THE SIZE AND LOCATION OF ALL SLAB OPENINGS WITH ALL RELATED DISCIPLINES. CONTRACTOR SHALL SUBMIT PROPOSED LOCATIONS OF CORE DRILLING AND SLAB OPENINGS TO ARCHITECT AND STRUCTURAL ENGINEER OF RECORD FOR REVIEW AND APPROVAL PRIOR TO PROCEEDING WITH THE WORK.
M. PATCH, REPAIR, AND INSTALL ALL FIREPROOFINGS AS REQUIRED BY CODE. FIREPROOF ALL NEW PENETRATIONS AS REQUIRED FOR APPROVAL BY THE AUTHORITY HAVING JURISDICTION.
N. WHERE BUILDING THERMAL EXPANSION JOINTS ARE REQUIRED, CONTRACTOR SHALL COMPLY WITH APPLICABLE CODE AND INDUSTRY BEST PRACTICES FOR ROUTING OF ALL PIPING, DUCTS, CONDUITS AND OTHER CONTINUOUS RUNS.
O. CONTRACTOR SHALL CONTINUOUSLY CHECK ARCHITECTURAL AND STRUCTURAL CLEARANCES FOR ACCESSIBILITY OF EQUIPMENT AND MECHANICAL AND ELECTRICAL SYSTEMS. NO ALLOWANCES OF ANY KIND WILL BE MADE FOR THE GENERAL CONTRACTOR'S NEGLIGENCE TO FORESEE MEANS OF INSTALLING EQUIPMENT INTO POSITION.
P. FINISHED WORK SHALL BE FIRM, WELL-ANCHORED, IN TRUE ALIGNMENT, PLUMB, LEVEL, WITH SMOOTH, CLEAN, UNIFORM APPEARANCE WITHOUT WAVES, DISTORTIONS, HOLES, MARKS, CRACKS, STAINS, OR DISCOLORATION. JOINTING SHALL BE CLOSE FITTING, NEAT AND WELL SCURED. FINISHED WORK SHALL HAVE NO EXPOSED UNSIGHTLY ANCHORS OR FASTENERS AND SHALL NOT PRESENT HAZARDOUS, UNSAFE CORNERS. ALL WORK SHALL HAVE THE PROVISION FOR EXPANSION, CONTRACTION AND SHRINKAGE AS NECESSARY TO PREVENT CRACKS, BUCKLING, AND WARPING DUE TO TEMPERATURE AND HUMIDITY CONDITIONS.
Q. ATTACHMENTS, CONNECTIONS OR FASTENERS OF ANY NATURE ARE TO PROPERLY AND PERMANENTLY BE SECURED IN CONFORMANCE WITH INDUSTRY BEST PRACTICES. THE DRAWINGS HIGHLIGHT SPECIAL CONDITIONS ONLY AND BY NO MEANS ILLUSTRATE EVERY CONNECTION. THE CONTRACTOR IS RESPONSIBLE FOR IMPROVING CONNECTION ACCORDINGLY.
R. CONTRACTOR SHALL WAIVE 'COMMON PRACTICE' AND 'COMMON USAGE' AS CONSTRUCTION CRITERIA WHEREVER DETAILS AND CONTRACT DOCUMENTS OR GOVERNING CODES, ORDINANCES, ETC. REQUIRE QUANTITY OR BETTER QUALITY THAN 'COMMON PRACTICE' OR 'COMMON USAGE' WOULD REQUIRE.
S. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND SUBMITTALS AND SHALL ORDER AND SCHEDULE DELIVERY OF MATERIALS TO AVOID DELAYS IN CONSTRUCTION. IF AN ITEM IS FOUND TO BE UNAVAILABLE OR TO HAVE A LONG LEAD TIME, THE GENERAL CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY WITH A PROPOSED ALTERNATIVE.
T. CONTRACTOR SHALL NOTIFY THE OWNER, THE LANDLORD, AND THE ARCHITECT IN WRITING OF ANY DEFICIENCIES IN BASE BUILDING WORK PRIOR TO THE COMMENCEMENT OF THE WORK. ANY UNREPORTED DEFICIENCIES WILL BECOME THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO CORRECT.
U. CONTRACTOR SHALL EXERCISE INDUSTRY BEST PRACTICES FOR CARE AND CAUTION DURING THE CONSTRUCTION OF THE WORK, AND SHALL SCHEDULE WORK TO MINIMIZE DISTURBANCES TO OCCUPANTS. ADJACENT SPACES AND/OR STRUCTURES, PROPERTY, PUBLIC THOROUGHFARES, ETC. THE GENERAL CONTRACTOR SHALL TAKE PRECAUTIONS AND BE RESPONSIBLE FOR THE SAFETY OF ALL BUILDING OCCUPANTS DURING CONSTRUCTION PROCEDURES. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COSTS INCURRED.
V. ALL DEBRIS SHALL BE REMOVED FROM THE SITE ON A DAILY BASIS, OR AS DIRECTED BY THE AUTHORITY HAVING JURISDICTION. UPON COMPLETION OF THE WORK, REMOVE ALL DEBRIS FROM THE WORK PROVIDED UNDER THIS CONTRACT AND LEAVE ALL AREAS CLEAN. TRASH IS NOT PERMITTED TO BE BURNED ON SITE.
W. ALL ABANDONED AND MISCELLANEOUS NAILS, HANGERS, STAPLES, WIRES, CONDUITS AND DEBRIS SHALL BE REMOVED FROM EXPOSED AREAS OF THE FLOORS, WALLS, AND CEILING. REMOVE ALL ABANDONED PIPE SLEEVES IN FLOOR SLABS. PATCH EXISTING SLAB AS REQUIRED TO MAINTAIN UL FIRE RATING OF FLOOR SLAB WHERE PIPES AND CONDUITS HAVE BEEN REMOVED.
X. SLAB PENETRATIONS SHALL BE SEALED AS REQUIRED TO MAINTAIN FIRE RATING, USING MATERIALS AND METHODS APPROVED BY THE AUTHORITY HAVING JURISDICTION. EXPANSION MATERIAL SHALL BE APPROVED BY THE ARCHITECT.
Y. CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY ACCESS PANELS WHICH MAY BE REQUIRED PRIOR TO PROCEEDING WITH THE WORK. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL TRADES. REQUIRED ACCESS PANELS SHALL BE INCLUDED IN THE CONTRACTOR'S SCOPE OF WORK.
Z. CONTRACTOR SHALL PROVIDE THE TEAM WITH A CONSTRUCTION SCHEDULE SHOWING THE PROPOSED PHASING. LONG LEAD ITEMS THAT WILL AFFECT THE SUBSTANTIAL COMPLETION DATE SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.

PBK ARCHITECTS logo and contact information for SAN ANTONIO, TX. Includes address, phone, fax, and website details.

ISSUE FOR CONSTRUCTION


PROJECT GRAPHIC REFERENCES



PROJECT GRAPHIC REFERENCES

Table of project graphic references including symbols for plan north, true north, working point, fire rating type, core structural width type, composition type, partition type tag, BLDG AREA LEVEL, ROOM NAME, EXIT SIGN, MATCHLINE VIEW REFERENCE, CURTAINWALL TAG, KEYNOTE TAG, WINDOW & LOUVER TAG, MATERIAL TAG, REVISION TAG, and CASEWORK TYPE.

VICINITY MAP



PROJECT LOCATION

CHECKED BY: Checker

PLOT Stamp: 6/14/2024 8:13:46 AM










Table with project information: CLIENT (Alamo Colleges), DATE (2024/06/14), PROJECT NUMBER (230462), and DRAWING HISTORY.






ISSUE FOR CONSTRUCTION BUILDING NUMBER 1

GENERAL PROJECT INFORMATION





G-002



24 TEXAS ACCESSIBILITY STANDARDS
 1/4" = 1'-0"



DESCRIPTION	Agnes 13 - Adult (Grades 8 and Above)
WATER CLOSET: To Top of Seat	17" - 19"
Grab Bar Height	33" - 38"
Flush Control Height	25" TYP 44" MAX
URINAL: Max. To Rim of Basin	17"
Flush Control Height (Max)	44"
LAVATORIES: Front Approach	27"
Knee Clearance (Min)	27"
To Top (Max)	34"
To Faucet (Max)	29"
FIXED OR BUILT-IN: Height of Tables or Counter	28" - 34"
Knee Clearance (Min)	27"
SHELVES, DISPENSERS: Max. Height to Control Device	48"
Frontal Approach (Max)	48"
Side Approach (Max)	48"
DRINKING FOUNTAINS: To Spout (Max)	36"
Knee Clearance (Min)	27"
SWITCHES AND CONTROLS: Frontal Approach (Max)	48"
Side Approach (Max)	48"
MIRRORS: Max. Height to Bottom of Reflective Surface at Lavatories and Counter Tops	40"
Full Length	35"
MIRRORS: Min. Height to Top of Reflective Surface	74"
Full Length	74"
TOILET PAPER DISPENSER: Height to Center of Roll (Max)	19"
PAPER TOWEL DISPENSER: Height to Operating Mechanism	48"
SHOWER: Top of Seat	17" - 19"
Grab Bar	33" - 38"
To Hand Shower Head Mounting (Max)	48"



Sheet Grids Template
Z400
FOR BLUEBAM LABELING OOR




ISSUE FOR PERMIT



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Milam St.
San Antonio, TX 78203
ISSUE FOR PERMIT





CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/06/12		
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

SITE PLAN

C200





LEGEND	
[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT

PARKING TABLE	
ITEM	QUANTITY
EXISTING PARKING SPOTS	125
EXISTING ADA SPOTS	9
REQUIRED ADA SPOTS	4
PROPOSED PARKING SPOTS	81
PROPOSED ADA SPOTS	8

IMPERVIOUS COVER COMPARISON			
	PERVIOUS	IMPERVIOUS	TOTAL
EXISTING	15497.11	66628.36	82125.47
PROPOSED	6426.58	75698.89	82125.47
IMPERVIOUS INCREASE		9070.53	

CHECKED BY: SH & AL
DRAWN BY: JC

ISSUE FOR CONSTRUCTION



LEGEND

[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PAE PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PUE PROPOSED UTILITY EASEMENT

FIRE PROTECTION INFO

OWNER:	ST. PHILLIPS COLLEGE
SITE AREA (SF)	21,863
NO. OF STORIES	1
PROPOSED BUILDING	TOTAL GSF HEIGHT TYPE
	26,114 38 ft IIB
TOTAL REQUIRED FLOW (GPM)	3,500
BUILDING SPRINKLER SYSTEM:	YES
REDUCTION DUE TO SPRINKLERS:	75%
FINAL REQUIRED FIRE FLOW	875
AVAILABLE FLOW @ 20 PSI (GPM)	940






ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

ARCHITECT: BA & ARCHITECTS
1313 W. Loop West
Suite 100
San Antonio, TX 78204
210-492-1000
LINDY & HARRIS ENGINEERING
1313 W. Loop West
Suite 100
San Antonio, TX 78204
210-492-1000
MEASUREMENTS
1313 W. Loop West
Suite 100
San Antonio, TX 78204
210-492-1000

WFAC Black Box Addition PKG 1

600 S. Miltman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT: Alamo Colleges

DATE: 2024/06/12 PROJECT NUMBER: 230462



No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

SITE FIRE PLAN

ISSUE FOR CONSTRUCTION





LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT REF. STRUCTURAL
	PROPOSED 4" CONCRETE SIDEWALK
	PROPOSED BUILDING
	EXISTING PAVEMENT EDGE
	PROPERTY LINE
	EXISTING EASEMENT
	PROPOSED EASEMENT
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EX. PROP. STORM LINE
	EX. PROP. WATER LINE
	EX. PROP. SANITARY SEWER LINE
	EXISTING THERMALS
	PROPOSED THERMALS
	EX. PROP. GAS LINE
	EX. PROP. DATA/TELECOM
	EX. PROP. UNDERGROUND ELECTRIC
	EX. PROP. FIBER OPTIC
	EX. PROP. OVERHEAD ELECTRIC
	EX. PROP. FIRE HYDRANT EXPANSION JOINT
	EX. PROP. WATER METER CONTRACTION JOINT
	EX. PROP. GATE VALVE
	EX. IRRIGATION CONTROL VALVE
	PROP. FIRE DEPARTMENT CONNECTION
	PROP. POST INDICATOR VALVE
	PROP. HOSE LAY
	EX. PROP. SANITARY SEWER MANHOLE
	EX. PROP. SANITARY SEWER CLEANOUT
	EX. STORM SEWER MANHOLE
	PROP. STORM SEWER CURB INLET
	EX. PROP. LIGHT POLE
	PROPOSED PUBLIC ACCESS EASEMENT
	PROPOSED UTILITY EASEMENT



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER
DIMENSION CONTROL & PAVING PLAN

C202

ISSUE FOR CONSTRUCTION

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.

SCALE: 1"= 20'




ARCHITECT		SAN ANTONIO		PBK Architects, Inc.	
601 N.W. Loop 410, Suite 400		San Antonio, TX 78216		210-829-0123 P.	
210-829-0578 F		TX Firm: BR 1608		REGISTERED PROFESSIONALS	
ARCHITECT		SAN ANTONIO		PBK Architects, Inc.	
601 N.W. Loop 410, Suite 400		San Antonio, TX 78216		210-829-0123 P.	
210-829-0578 F		TX Firm: BR 1608		REGISTERED PROFESSIONALS	
ARCHITECT		SAN ANTONIO		PBK Architects, Inc.	
601 N.W. Loop 410, Suite 400		San Antonio, TX 78216		210-829-0123 P.	
210-829-0578 F		TX Firm: BR 1608		REGISTERED PROFESSIONALS	

LEGEND

- PROP. TREE PROTECTION FENCE
- EX. TREE TO BE REMOVED
- EX. TREE TO REMAIN
- DEMOLITION AREA

WFAC Black Box Addition PKG 1

600 S. Miltman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



STATE OF TEXAS
ANDREW A. LANGE
118770
06/14/2024

CLIENT: Alamo Colleges

DATE: 2024/06/12 PROJECT NUMBER: 230462


No.	Description	Date

ISSUE FOR CONSTRUCTION


BUILDING NUMBER

**EXISTING
CONDITIONS & DEMO
PLAN**

C300





CHECKED BY: SH & AL
DRAWN BY: JC



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
PROJECT ARCHITECT	BA & ARCHITECTS
1515 N. LOOP WEST SUITE 100 SAN ANTONIO, TX 78201 210-462-0000 WWW.BAANDARCHITECTS.COM	
LANDSCAPE ARCHITECT	LANDSCAPE ARCHITECTS
11111 W. LOOP WEST SUITE 100 SAN ANTONIO, TX 78240 210-492-0000 WWW.LANDSCAPEARCHITECTS.COM	
ENGINEERING	LUNDY & HARRIS ENGINEERING
11111 W. LOOP WEST SUITE 100 SAN ANTONIO, TX 78240 210-492-0000 WWW.LUNDYHARRIS.COM	
PROFESSIONAL SEAL	MEASUREMENTS
11111 W. LOOP WEST SUITE 100 SAN ANTONIO, TX 78240 210-492-0000 WWW.MEASUREMENTS.COM	

WFAC Black Box Addition PKG 1


600 S. Miltman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION





CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER		

GRADING PLAN

C400



ISSUE FOR CONSTRUCTION



LEGEND

- 340 --- EXISTING CONTOURS
- (340) PROPOSED CONTOURS
- PROPERTY LINE
- PROPOSED SWALE WITH DIRECTION OF FLOW ARROWS
- GRADE BREAK
- BR PROPOSED FINISHED GRADE AT BOTTOM OF RAMP
- BS PROPOSED FINISHED GRADE AT BOTTOM OF STAIR
- BW PROPOSED FINISHED GRADE AT BASE OF WALL
- FG PROPOSED FINISHED GRADE ELEVATION
- FL PROPOSED FLOWLINE ELEVATION
- G PROPOSED GUTTER FLOWLINE ELEVATION
- GB PROPOSED GRADE BREAK
- JB PROPOSED TOP OF JUNCTION BOX ELEVATION
- ME @ SW MATCH EXISTING SIDEWALK ELEVATION
- ME @ TC MATCH EXISTING TOP OF CURB ELEVATION
- ME @ TP MATCH EXISTING TOP OF PAVEMENT ELEVATION
- SW PROPOSED TOP OF PAVEMENT AT SIDEWALK ELEVATION
- TC PROPOSED TOP OF CURB ELEVATION
- TG PROPOSED TOP OF GRATE ELEVATION
- TP PROPOSED TOP OF PAVEMENT ELEVATION
- TR PROPOSED TOP OF RAMP ELEVATION
- TW PROPOSED TOP OF WALL ELEVATION
- TMS PROPOSED TOP MUD SLAB
- BMS PROPOSED BOTTOM OF MUD SLAB






ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-0578 F
TX Firm BR 1608

ASSOCIATE ARCHITECT BA & ARCHITECTS
1111 N. LOOP WEST
SUITE 1000
SAN ANTONIO, TEXAS 78205
210-441-0000
LINDY & TRAVIS ENGINEERING
1111 N. LOOP WEST
SUITE 1000
SAN ANTONIO, TEXAS 78205
210-441-0000
PROFESSOR
MEAN PROFESSIONALS
1111 N. LOOP WEST
SUITE 1000
SAN ANTONIO, TEXAS 78205

WFAC Black Box Addition PKG 1

600 S. Mittman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER

CRAWLSPACE



C401

ISSUE FOR PERMIT



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608


WFAC Black Box Addition PKG 1
600 S Milman St.
San Antonio, TX 78203
ISSUE FOR PERMIT




CLIENT		Alamo Colleges
DATE	2024/06/12	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER
PRE DRAINAGE AREA MAP

C500



LEGEND	
	DRAINAGE AREA BOUNDARY
	DRAINAGE AREA LABEL AND FLOW DIRECTION
	PROPERTY LINE
	EXISTING CONTOURS
	PROPOSED CONTOURS
	FLOW PATH



Pre AREA A					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	23001.03	0.53	0.50
Grass Cover	Grass Cover > 75%	0.35	5475.37	0.13	0.04
TOTAL			28476.40	0.65	0.55
					C 0.83
Pre AREA B					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	38420.17	0.88	0.84
Grass Cover	Grass Cover > 75%	0.35	6070.51	0.14	0.05
TOTAL			44490.68	1.02	0.89
					C 0.87
Pre AREA C					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5207.16	0.12	0.11
Grass Cover	Grass Cover > 75%	0.35	3951.23	0.09	0.03
TOTAL			9158.39	0.21	0.15
					C 0.70



PRE DEVELOPMENT PEAK RUNOFF							
AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.65	0.83	5.0	2.9	4.2	5.9	7.4
B	1.02	0.87	5.0	4.7	7.0	9.7	12.2
C	0.21	0.70	9.0	0.7	1.0	1.3	1.6

Time (minutes)	Atlas 14 Rainfall Intensity (in/hr)			
	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05

Pre					
Area A		Area B		Area C	
C	0.83	C	0.87	C	0.70
Area (ac)	0.65	Area (ac)	1.02	Area (ac)	0.21
Flow Length (ft)	315.12	Flow Length (ft)	479.97	Flow Length (ft)	70.70
SCS Sheet Flow (ft)	68.20	SCS Sheet Flow (ft)	85.32	SCS Sheet Flow (ft)	47.40
Slope (%)	1.02	Slope (%)	1.28	Slope (%)	1.78
Manning's Roughness	0.013	Manning's Roughness	0.013	Manning's Roughness	0.300
Flow Time (min)	1.06	Flow Time (min)	1.16	Flow Time (min)	8.91
SCS Shallow Concentrated Flow (ft)	246.92	SCS Shallow Concentrated Flow (ft)	180.17	SCS Sheet Flow (ft)	23.30
PAVEMENT		PAVEMENT		Slope (%)	1.57
Slope (%)	1.00	Slope (%)	0.86	Manning's Roughness	0.011
Velocity (ft/s)	2.03	Velocity (ft/s)	1.89	Flow Time (min)	0.38
Flow Time (min)	2.03	Flow Time (min)	1.59	Time of Concentration (min)	9.00
Time of Concentration (min)	3.09	SCS Channel Flow (ft)	153.60	*COSA requires min TOC of 5 min*	
COSA requires min TOC of 5 min		Slope (%)	0.21		
		Manning's Roughness	0.012		
		Velocity (ft/s)	2.95		
		Flow Time (min)	0.85		
		SCS Channel Flow (ft)	60.88		
		Slope (%)	1.79		
		Manning's Roughness	0.011		
		Velocity (ft/s)	6.50		
		Flow Time (min)	0.10		
		Time of Concentration (min)	3.70		
		COSA requires min TOC of 5 min			

ISSUE FOR PERMIT

Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.



LEGEND

- DRAINAGE AREA BOUNDARY
- (A1) DRAINAGE AREA LABEL AND FLOW DIRECTION
- - - - - PROPERTY LINE
- - - - - EXISTING CONTOURS
- - - - - PROPOSED CONTOURS
- FLOW PATH

Required Storage	
Storm Event	Required Storage (ft ³)
1 - Year	2037.00
5 - Year	2784.00
25 - Year	3698.00
100 - Year	4549.00




ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

600 S Milburn St.
San Antonio, TX 78203

ISSUE FOR PERMIT



CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/06/12		

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

POST DRAINAGE AREA MAP

C501

POST AREA A					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	2700.94	0.06	0.06
Grass Cover	Grass Cover > 75%	0.35	54.6	0.00	0.00
TOTAL			2755.54	0.06	0.06
			C		0.94

POST AREA B					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	67228.61	1.54	1.47
Grass Cover	Grass Cover > 75%	0.35	4672.06	0.11	0.04
TOTAL			71900.67	1.65	1.50
			C		0.91

POST AREA C					
COVER TYPE	SURFACE DESCRIPTION	C	AREA (SF)	AREA (AC)	C x AREA
Impervious Areas	Paved parking lots, roofs driveways etc.	0.95	5769.34	0.13	0.13
Grass Cover	Grass Cover > 75%	0.35	1699.92	0.04	0.01
TOTAL			7469.26	0.17	0.14
			C		0.81

POST DEVELOPMENT PEAK RUNOFF							
AREA	SIZE (AC)	C	TC (MIN)	1 YR (CFS)	5 YR (CFS)	25 YR (CFS)	100 YR (CFS)
A	0.06	0.94	5.0	0.3	0.4	0.6	0.8
B	1.65	0.91	5.0	8.2	12.2	16.9	21.2
C	0.17	0.81	8.0	0.6	0.9	1.3	1.6

Time (minutes)	Atlas 14 Rainfall Intensity (in/hr)			
	1 - YEAR	5 - YEAR	25 - YEAR	100 - YEAR
5	5.29	7.88	11.00	13.79
6	5.07	7.45	10.43	13.08
7	4.86	7.11	9.95	12.49
8	4.64	6.81	9.54	11.97
9	4.43	6.54	9.17	11.49
10	4.21	6.30	8.82	11.05

Post			
Area A	Area B	Area C	
C	0.94	C	0.91
Area (ac)	0.06	Area (ac)	1.65
Flow Length (ft)	29.10	Flow Length (ft)	416.77
SCS Sheet Flow (ft)	29.10	SCS Sheet Flow (ft)	85.32
Slope (%)	0.99	Slope (%)	1.28
Manning's Roughness	0.011	Manning's Roughness	0.013
Flow Time (min)	0.54	Flow Time (min)	1.32
Time of Concentration (min)	0.54	SCS Shallow Concentrated Flow (ft)	81.23
COSA requires min TOC of 5 min			
PAVEMENT			
Slope (%)	0.65	SCS Sheet Flow (ft)	32.46
Velocity (ft/s)	1.64	Slope (%)	2.55
Flow Time (min)	0.83	Manning's Roughness	0.011
SCS Channel Flow (ft)	224.55	Flow Time (min)	0.40
Slope (%)	0.50	Time of Concentration (min)	8.00
Manning's Roughness	0.011	*COSA requires min TOC of 5 min*	
Velocity (ft/s)	5.00		
Flow Time (min)	0.74		
SCS Channel Flow (ft)	25.67		
Slope (%)	0.50		
Manning's Roughness	0.011		
Velocity (ft/s)	7.00		
Flow Time (min)	0.06		
Time of Concentration (min)	2.95		
COSA requires min TOC of 5 min			

CHECKED BY: SH & AL
DRAWN BY: JC



ISSUE FOR PERMIT

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
SAN ANTONIO 1301 BRASS LANDSCAPE DESIGN GROUP 113 W. 10th St. SAN ANTONIO, TX 78205 LUNDY & HARRIS ENGINEERING 113 W. 10th St. SAN ANTONIO, TX 78205 T. 210-225-7500 PROLOGUE NEAR PRODUCE 113 W. 10th St. SAN ANTONIO, TX 78205 T. 210-225-7500	

WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges
DATE	2024/06/12
PROJECT NUMBER	230462


No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

BUILDING NUMBER

OVERALL UTILITY



C600




LEGEND

	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT
	PROPOSED BUILDING
	EXISTING PAVEMENT EDGE
	PROPERTY LINE
	EXISTING EASEMENT
	PROPOSED EASEMENT
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EX. PROP. STORM LINE
	EX. PROP. WATER LINE
	EX. PROP. SANITARY SEWER LINE
	EXISTING THERMALS
	PROPOSED THERMALS
	EX. PROP. GAS LINE
	EX. PROP. DATA/TELECOM
	EX. PROP. UNDERGROUND ELECTRIC
	EX. PROP. FIBER OPTIC
	EX. PROP. OVERHEAD ELECTRIC
	EX. PROP. FIRE HYDRANT
	EX. PROP. WATER METER
	EX. PROP. GATE VALVE
	EX. IRRIGATION CONTROL VALVE
	PROP. FIRE DEPARTMENT CONNECTION
	PROP. POST INDICATOR VALVE
	PROP. HOSE LAY
	EX. PROP. SANITARY SEWER MANHOLE
	EX. PROP. SANITARY SEWER CLEANOUT
	EX. STORM SEWER MANHOLE
	PROP. STORM SEWER CURB INLET
	EX. PROP. LIGHT POLE
	PROPOSED PUBLIC ACCESS EASEMENT
	PROPOSED UTILITY EASEMENT


ISSUE FOR CONSTRUCTION



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING
UTILITY INVERTS PRIOR TO CONSTRUCTION



EL-02
SCALE: 1"=20' H, 1"=5' V





FO-01
SCALE: 1"=20' H, 1"=5' V

LEGEND	
[Symbol]	PROPOSED ASPHALT PAVEMENT
[Symbol]	PROPOSED STRUCTURAL PAVEMENT
[Symbol]	REF. STRUCTURAL
[Symbol]	PROPOSED 4" CONCRETE SIDEWALK
[Symbol]	PROPOSED BUILDING
[Symbol]	EXISTING PAVEMENT EDGE
[Symbol]	PROPERTY LINE
[Symbol]	EXISTING EASEMENT
[Symbol]	PROPOSED EASEMENT
[Symbol]	EXISTING CONTOURS
[Symbol]	PROPOSED CONTOURS
[Symbol]	EX. PROP. STORM LINE
[Symbol]	EX. PROP. WATER LINE
[Symbol]	EX. PROP. SANITARY SEWER LINE
[Symbol]	EXISTING THERMALS
[Symbol]	PROPOSED THERMALS
[Symbol]	EX. PROP. GAS LINE
[Symbol]	EX. PROP. DATA/TELECOM
[Symbol]	EX. PROP. UNDERGROUND ELECTRIC
[Symbol]	EX. PROP. FIBER OPTIC
[Symbol]	EX. PROP. OVERHEAD ELECTRIC
[Symbol]	EX. PROP. FIRE HYDRANT
[Symbol]	EX. PROP. WATER METER
[Symbol]	EX. PROP. GATE VALVE
[Symbol]	EX. IRRIGATION CONTROL VALVE
[Symbol]	PROP. FIRE DEPARTMENT CONNECTION
[Symbol]	PROP. POST INDICATOR VALVE
[Symbol]	PROP. HOSE LAY
[Symbol]	EX. PROP. SANITARY SEWER MANHOLE
[Symbol]	EX. PROP. SANITARY SEWER CLEANOUT
[Symbol]	EX. STORM SEWER MANHOLE
[Symbol]	PROP. STORM SEWER CURB INLET
[Symbol]	EX. PROP. LIGHT POLE
[Symbol]	PROPOSED PUBLIC ACCESS EASEMENT
[Symbol]	PROPOSED UTILITY EASEMENT



ARCHITECT
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1



STATE OF TEXAS
ANDREW A. LANGE
118770
06/14/2024

CLIENT		
Alamo Colleges	PROJECT NUMBER	230462
DATE	2024/06/12	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER

ELEC. & COMMS
PLAN & PROFILES

C700




Sheet Grids Template
Z:400
FOR BLUEBAM LABELING CORR.

ISSUE FOR PERMIT



ARCHITECT	PBK Architects, Inc.
PROJECT	WFAC Black Box Addition
DATE	08/05/2024
SCALE	1"=20'
PROJECT NO.	230462
DATE	08/05/2024
DESCRIPTION	ADDENDUM 1

PROPOSED ASPHALT PAVEMENT	PROPOSED STRUCTURAL PAVEMENT	PROPOSED 4" CONCRETE SIDEWALK	PROPOSED BUILDING
EXISTING PAVEMENT EDGE	PROPERTY LINE	EXISTING EASEMENT	PROPOSED EASEMENT
EXISTING CONTOURS	PROPOSED CONTOURS	EX. PROP. STORM LINE	EX. PROP. WATER LINE
EX. PROP. SANITARY SEWER LINE	EXISTING THERMALS	PROPOSED THERMALS	EX. PROP. GAS LINE
EX. PROP. DATA/TELECOM	EX. PROP. UNDERGROUND ELECTRIC	EX. PROP. FIBER OPTIC	EX. PROP. OVERHEAD ELECTRIC
EX. PROP. FIRE HYDRANT	EX. PROP. WATER METER	EX. PROP. GATE VALVE	EX. IRRIGATION CONTROL VALVE
PROP. FIRE DEPARTMENT CONNECTION	PROP. POST INDICATOR VALVE	PROP. HOSE LAY	EX. PROP. SANITARY SEWER MANHOLE
EX. PROP. SANITARY SEWER CLEANOUT	EX. STORM SEWER MANHOLE	PROP. STORM SEWER CURB INLET	EX. PROP. LIGHT POLE
PROPOSED PUBLIC ACCESS EASEMENT	PROPOSED UTILITY EASEMENT		




CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT
BUILDING NUMBER

STORM PLAN

C800



CHECKED BY: SH & AL
DRAWN BY: JC

ISSUE FOR PERMIT

Sheet Grids Template
2400
FOR BLUEBEAM LABELING CORR.

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT PBK Architects, Inc.

601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-823-0123 P
210-823-0578 F
TX Firm BR 160B

REGISTERED PROFESSIONAL ARCHITECT
STATE OF TEXAS
NO. 131,998

REGISTERED PROFESSIONAL ARCHITECT
STATE OF TEXAS
NO. 131,998







REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
NO. 124,441

REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
NO. 124,441

REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
NO. 124,441

REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
NO. 124,441

NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION




WFAC Black Box Addition PKG 1

600 S Millman St.
San Antonio, TX 78203

ISSUE FOR PERMIT

ALAMO COLLEGES
ST. PHILLIP'S COLLEGE



CLIENT		Alamo Colleges	
DATE	2024/06/12	PROJECT NUMBER	230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

BUILDING NUMBER

STORM PROFILES

C801

CHECKED BY:
SH & AL
DRAWN BY:
JC

ISSUE FOR PERMIT


Sheet Grids Template
Z400
FOR BLUEBAM LABELING.COR.

CAUTION: CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION.
CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	BA & ARCHITECTS
DESIGNER	BA & ARCHITECTS
LANDSCAPE	BA & ARCHITECTS
STRUCTURAL	BA & ARCHITECTS
MECHANICAL/ELECTRICAL/PLUMBING	BA & ARCHITECTS
TRAFFIC	BA & ARCHITECTS
PROVIDER	BA & ARCHITECTS
MEASURER	BA & ARCHITECTS
DATE	08/05/2024

WFAC Black Box Addition PKG 1





CLIENT	Alamo Colleges	
DATE	2024/06/12	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT

DETENTION PLAN



C802



CHECKED BY: SH & AL
DRAWN BY: JC

Sheet Grids Template
FOR BLUEBRAIN LABELING CORR.


ISSUE FOR CONSTRUCTION



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION

LEGEND

- PROPOSED ASPHALT PAVEMENT
- PROPOSED STRUCTURAL PAVEMENT REF. STRUCTURAL
- PROPOSED 4" CONCRETE SIDEWALK
- PROPOSED BUILDING
- EXISTING PAVEMENT EDGE
- PROPERTY LINE
- EXISTING EASEMENT
- PROPOSED EASEMENT
- EXISTING CONTOURS
- PROPOSED CONTOURS
- EX. | PROP. STORM LINE
- EX. | PROP. WATER LINE
- EX. | PROP. SANITARY SEWER LINE
- EXISTING THERMALS
- PROPOSED THERMALS
- EX. | PROP. GAS LINE
- EX. | PROP. DATA/TELECOM
- EX. | PROP. UNDERGROUND ELECTRIC
- EX. | PROP. FIBER OPTIC
- EX. | PROP. OVERHEAD ELECTRIC
- EX. | PROP. FIRE HYDRANT
- EX. | PROP. WATER METER
- EX. | PROP. GATE VALVE
- EX. IRRIGATION CONTROL VALVE
- PROP. FIRE DEPARTMENT CONNECTION
- PROP. POST INDICATOR VALVE
- PROP. HOSE LAY
- EX. | PROP. SANITARY SEWER MANHOLE
- EX. | PROP. SANITARY SEWER CLEANOUT
- EX. STORM SEWER MANHOLE
- PROP. STORM SEWER CURB INLET
- EX. | PROP. LIGHT POLE
- PAE PROPOSED PUBLIC ACCESS EASEMENT
- PUE PROPOSED UTILITY EASEMENT



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

ARCHITECT BA & ARCHITECTS
1700 S. W. Loop
COLUMBIA
LANDSCAPE
ROSE LAND GROUP
1713 W. Loop
TEXAS
LUNY & TRAVIS ENGINEERING
1713 W. Loop
TEXAS
TRAVIS
NEAR PROJECTIONS
1713 W. Loop
TEXAS
TRAVIS

WFAC Black Box Addition PKG 1

600 S. Mittman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION

ALAMO COLLEGES
ST. PHILIP'S COLLEGE

KEY PLAN
NORTH PLAN TRUE

STATE OF TEXAS
ANDREW A. LANGE
118770
06/14/2024

DRAWING HISTORY		
No.	Description	Date



CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

ISSUE FOR CONSTRUCTION
BUILDING NUMBER

SANITARY PLAN & PROFILES




C900

CHECKED BY:
SH & AL
DRAWN BY:
JC



NOTE:
CONTRACTOR TO FIELD VERIFY EXISTING UTILITY INVERTS PRIOR TO CONSTRUCTION

LEGEND	
	PROPOSED ASPHALT PAVEMENT
	PROPOSED STRUCTURAL PAVEMENT





118770
06/14/2024

CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/06/12		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER

WATER PLAN & PROFILES

ISSUE FOR CONSTRUCTION



LEGEND

	CONSTRUCTION ENTRANCE, INSTALLED PER DETAIL
	PROPERTY LINE
	EXISTING CONTOURS
	PROPOSED CONTOURS
	EXISTING FLOW PATH
	PROPOSED FLOW PATH
	SILT FENCE, INSTALLED PER DETAIL
	PROPOSED DAM EROSION CONTROL, LOG-18"
	PROPOSED ROCK FILTER DAM TYPE 3
	PROP. TREE PROTECTION FENCE
	PROP. TREE PROTECTION FENCE

EROSION CONTROL NOTES:
OWNER INFORMATION: ST PHILLIPS COLLEGE
PROJECT NAME: ST PHILLIPS COLLEGE WATSON FINE ARTS CENTER BLACK BOX ADDITION
PROJECT LOCATION: 600 S MITTMAN ST. SAN ANTONIO, TX 78203

LATITUDE: 29°24'49.57"N
 LONGITUDE: 98°27'14.61"W
 TOTAL SITE AREA IS: 1.89 ACRES
 TOTAL AREA OF SITE EXPECTED TO BE DISTURBED: 1.35 ACRES

EXISTING SITE CONDITIONS
 LAND USE: HIGHER EDUCATION
 LAND COVER: ~90% IMPERVIOUS
 RECEIVING WATERS: SALADO CREEK
 SEGMENT NO. OF CLASSIFIED WATER BODY: SALADO CREEK
 BASIN NAME: SAN ANTONIO RIVER

SOIL INFORMATION
 HYDROLOGIC SOIL GROUP: D

POST DEVELOPED SITE CONDITIONS
 LAND USE: HIGHER EDUCATION
 ACADEMIC BLDG

NATURE OF ACTIVITIES
 ACADEMIC BLDG

- SEQUENCE OF MAJOR ACTIVITIES**
1. INSTALL SILT FENCE AT STOCK PILE AREAS
 2. CLEARING, GRADING, GENERAL CONSTRUCTION SITE
 3. INSTALL FILTER ELEMENTS IMMEDIATELY AFTER DISTURBANCE AND/OR GRADING OPERATIONS.
 4. AFTER ESTABLISHMENT OF GRASS, REMOVE ALL TEMPORARY EROSION CONTROL.
 5. SEED ALL AREAS NOT HAVING PERMANENT GRASS COVERAGE AFTER APPROVAL BY COUNTY INSPECTOR.

- GENERAL EROSION CONTROL NOTES**
1. ALL UTILITIES AND SERVICE LINES SHOWN ARE TAKEN FROM RECORD INFORMATION SUPPLIED BY THE UTILITY OWNER OR HORIZONTALLY LOCATED BY INDEPENDENT LOCATORS. CONTRACTOR IS RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN PLAN AND ACTUAL CONDITIONS PRIOR TO CONSTRUCTION. OWNER AND ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF INFORMATION OR DATA RELIED ON TO DEPICT UNDERGROUND FACILITIES. CONTRACTOR IS TO CONTACT OWNERS OF ALL UTILITIES AND SERVICE LINES WITHIN THE PROJECT AREA AND NOTIFY OF INTENT AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH FACILITY OWNERS, CONTRACTOR IS TO VERIFY THE EXACT LOCATION AND VERTICAL POSITIONING OF ALL PIPELINES, EXISTING UTILITIES, AND SERVICE LINES WITHIN THE PROJECT AREA WHETHER SHOWN ON THE PLANS OR NOT, AT LEAST 48 HOURS PRIOR TO CONSTRUCTION. CONTRACTOR IS TO MAINTAIN STRUCTURAL INTEGRITY OF ALL PIPELINES, ELECTRIC TRANSMISSION POLES AND LINES, PERMANENT AND TEMPORARY UTILITIES. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE DONE TO EXISTING UTILITY FACILITIES, PAVEMENT, ETC. AS A RESULT OF CLEARING/DIRTWORK ACTIVITIES.
 2. CONTRACTOR TO CONTACT TEXAS 811 AND LOCAL UTILITY PROVIDERS TO LOCATE EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTACT GESSNER ENGINEERING IF CONFLICTS OCCUR.
 3. ALL DISTURBED AREAS NOT TO BE PAVED ARE TO HAVE ESTABLISHMENT OF GRASS.
 4. ALL SWALE AREAS (BOTTOM WIDTHS & SIDE SLOPES) ARE TO BE PREPARED AND HYDROMULCHED FOR PERMANENT ESTABLISHMENT OF VEGETATION. PRIOR TO HYDROMULCHING OPERATIONS, CONTRACTOR TO REPLACE TOPSOIL TO A DEPTH OF 6". TOPSOIL IS TO BE DISKED TO A DEPTH OF AT LEAST 4" AND LIGHTLY COMPACTED. FINAL GRADES WITH ESTABLISHED VEGETATION SHALL BE AS CALLED OUT ON THE GRADING PLAN.
 5. CONTRACTOR IS TO MAINTAIN EROSION CONTROL AT ALL LOCATIONS OF CONSTRUCTION THROUGHOUT DURATION OF THE PROJECT AND UNTIL VEGETATION IS ESTABLISHED. INSURE SEDIMENT IS NOT TRANSPORTED DOWNSTREAM FROM PROJECT VIA GRAVEL FILTER BAGS AND SILT FENCE INSTALLATIONS. IF EXCESSIVE EROSION IS OBSERVED IN THE FIELD, ADDITIONAL EROSION CONTROLS SHALL BE INSTALLED.
 6. CONTRACTOR SHALL NOT ALLOW SEDIMENT TO ENTER THE DOWNSTREAM CHANNEL. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING OF THE DOWNSTREAM CHANNEL AREAS AND RESTORING TO ORIGINAL CONDITION, INCLUDING ESTABLISHMENT OF REVEGETATION SHOULD CONSTRUCTION SEDIMENT BE FOUND OUTSIDE THE LIMITS OF CONSTRUCTION.
 7. THE CONTRACTOR WILL REMOVE ALL EXCESS SOIL FROM CONSTRUCTION VEHICLES PRIOR TO EXITING THE SITE.
 8. THE CONTRACTOR SHALL UNDERTAKE PROPER METHODS TO REDUCE DUST GENERATION FROM THE SITE.
 9. THE CONTRACTOR MUST COMPLY WITH FEDERAL, STATE, AND LOCAL REGULATIONS REGARDING SEDIMENTS AND EROSION CONTROL.
 10. A COPY OF THIS PLAN MUST BE KEPT AT THE CONSTRUCTION FACILITY DURING THE ENTIRE CONSTRUCTION PERIOD.
 11. ALL FINISHED GRADES ARE TO BE HYDRO-MULCHED, SPOT SODDED OR SEEDED AND WATERED UNTIL GROWTH IS ESTABLISHED.
 12. CONTRACTOR IS RESPONSIBLE TO FILE THE NOTICE OF INTENT AND NOTICE OF TERMINATION WITH AUTHORITY HAVING JURISDICTION.






ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ASSISTANT ARCHITECT	BA ARCHITECTS
1711 W. Loop West San Antonio, TX 78207 210-441-0992 210-441-0993 LINDY & TRAVIS ENGINEERING	
1711 W. Loop West San Antonio, TX 78207 210-441-0992 210-441-0993 LINDY & TRAVIS ENGINEERING	
1711 W. Loop West San Antonio, TX 78207 210-441-0992 210-441-0993 LINDY & TRAVIS ENGINEERING	
1711 W. Loop West San Antonio, TX 78207 210-441-0992 210-441-0993 LINDY & TRAVIS ENGINEERING	

WFAC Black Box Addition PKG 1

600 S Mittman St.
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/06/12	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER

EROSION CONTROL

C1100

GENERAL NOTES

1. NEW PIPE TO BE SET FLUSH WITH INSIDE WALL OF STRUCTURE.











TABLE
SEWER SIZE VS. OPENING

SEWER SIZE (INCHES)	MANHOLE BASE DIAMETER
48"	36"
54"	36"
60"	42"
66" OR GREATER	48"




- NOTES:**
- SUBGRADE STABILIZATION SHALL BE PER GEOTECHNICAL RECOMMENDATIONS AND LIME/CEMENT SERIES BASED ON ACTUAL SUBGRADE CONDITIONS.
 - SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
 - SEAL ALL EXPANSION JOINTS WITH SEAL CAP AND CONTROL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS. USE SELF LEVELING JOINT SEALANT ADJACENT TO EXISTING PAVEMENT.

SIDEWALK EXPANSION JOINT
NTS






- NOTE:**
SIDEWALK JOINT SPACING PER LANDSCAPE ARCHITECT OR JOINT PLAN. IF NOT SPECIFIED, SPACING SHALL BE EQUAL TO SIDEWALK WIDTH WITH A MAXIMUM SPACING OF 8-FOOT.

CONCRETE PAVEMENT
NTS



- NOTES:**
- SEE PLANS FOR JOINT SPACING, COMPRESSIVE STRENGTH, PAVEMENT THICKNESS, AND REINFORCING.
 - SAW CUT OPERATIONS SHALL BEGIN AS SOON AS POSSIBLE AFTER CONCRETE PLACEMENT.
 - SEAL ALL JOINTS WITH SELF LEVELING JOINT SEALANT MATERIAL PER SPECIFICATIONS.



- A. SATISFACTORY SOILS**
MATERIAL EXCAVATED FROM THE DITCH, WHICH IS FREE OF ROCKS, LUMPS, CLODS, OR DEBRIS LARGER THAN TWO (2) INCHES IN THE LARGEST DIMENSION, COMPACTED TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NON-STRUCTURAL AREAS (IE. YARDS, PASTURES, EASEMENTS) AND TO A MINIMUM OF 90% OF MAXIMUM DENSITY AS DETERMINED BY ASTM D698 (STANDARD) AT A MOISTURE CONTENT WITHIN OPTIMUM TO 2% OF OPTIMUM UNDER NEW STREET AND PAVEMENT AREAS.
- B. BANK RUN SAND**
GRANULAR MATERIAL FREE OF DETRIMENTAL QUANTITIES OF CLAY, DEBRIS, OR ORGANIC MATERIAL. REFERENCE SPECIFICATION FOR REQUIREMENTS.
- C. CEMENT STABILIZED SAND**
MATERIALS SHALL BE TYPE PORTLAND CEMENT CONFORMING TO ASTM C150 AND CLEAN DURABLE SAND MEETING GRADING REQUIREMENTS FOR FINE AGGREGATES OF ASTM C33. THE CEMENT STABILIZED SAND SHALL HAVE A MINIMUM OF 10% CEMENT PER CUBIC YARD OF CEMENT STABILIZED SAND MIXTURE, BASED ON LOOSE DRY WEIGHT VOLUME (AT LEAST 2.5 SACKS OF CEMENT PER CUBIC YARD OF MIXTURE). COMPACT MIX TO 90% OF ASTM D698 WITH A MOISTURE CONTENT BETWEEN .2% TO 2% ABOVE OPTIMUM.
- D. PAVEMENT SUBGRADE**
REFERENCE PAVEMENT SECTION DETAIL AND SPECIFICATION FOR MATERIALS AND DEPTHS.

GENERAL NOTES:
ALL AREAS WHERE EXISTING VEGETATION AND GRASS COVER HAVE BEEN BARED BY CONSTRUCTION SHALL BE ADEQUATELY BLOCK SOODED OR HYDROMULCHED AND WATERED UNTIL GROWTH IS ESTABLISHED. IN DEVELOPED AREAS WHERE GRASS IS PRESENT, BLOCK SOO WILL BE REQUIRED. BARED AREAS SHALL BE SEEDED OR SOODED WITHIN 14 CALENDAR DAYS OF LAST DISTURBANCE.






APPROVED EROSION CONTROL MEASURES MUST BE INSTALLED DURING THE ENTIRE TIME THAT EARTH HAS BEEN BARED BY CONSTRUCTION AND SHALL STAY IN PLACE UNTIL ACCEPTABLE VEGETATIVE GROWTH IS ESTABLISHED AFTER CONSTRUCTION IS COMPLETE AND THEN REMOVED BY CONTRACTOR.

ALL EROSION CONTROL MEASURES SHOULD BE CLEANED OF SILT AFTER EVERY RAIN.

ESTABLISHMENT OF VEGETATION MAY BE A WARRANTY ITEM.




- NOTES:**
- FOR BEDDING AND TRENCHING WITHIN ALL PAVED AREAS SEE DETAILS FOR OPEN CUT STREETS.
 - ALL BEDDING & INSTALLATION OF HDPE PIPE SHALL BE IN ACCORDANCE WITH ANSII/AWA STANDARDS FOR HOPE PIPE COMPACTION SHALL BE ATTAINED BY MECHANICAL TAMPING.
 - RELATIVE COMPACTION SHALL BE TESTING IN THE PRESENCE OF THE ENGINEER.
 - DUST RESULTING FROM THE CONTRACTOR'S PERFORMANCE OF THE WORK, EITHER INSIDE OR OUTSIDE THE RIGHT-OF-WAY, SHALL BE CONTROLLED BY THE CONTRACTOR.
 - ALL TRENCHES SHALL BE BACK FILLED AND TEMPORARY PAVING OR PLATING PLACED AT THE END OF EACH WORKING DAY IN AREAS TO BE PAVED. PROTECT ALL OPEN TRENCHES AT THE END OF EACH WORKING DAY.
 - HOPE LINES WITH WELDED JOINTS MAY BE BACKFILLED PRIOR TO TESTING AT CONTRACTOR'S RISK.

BEDDING AND TRENCH FOR HDPE PIPE
NTS



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1



CLIENT Alamo Colleges
DATE 2024/06/12 PROJECT NUMBER 230462

No.	Description	Date
1	ADDENDUM 1	08/05/2024

ISSUE FOR PERMIT


DETAILS

C1200


ISSUE FOR CONSTRUCTION

GENERAL NOTES:


- FINELY DIVIDED EARTH FREE OF ROCK, LUMPS AND CLODS EXCEEDING 6" SHALL BE PLACED BY HAND, AND COMPACTED AROUND THE CAST IRON PIPE TO A DEPTH OF 12" OVER THE TOP OF THE PIPE BEFORE BACKFILL IS BEGUN BY ANY MECHANICAL EQUIPMENT.
- ALL CONCRETE BLOCKING SHALL BE - 28 DAY CONCRETE STRENGTH = 2000psi.
- ALL THRUST BLOCKING SHALL PROVIDE A MINIMUM OF 2 SQUARE FEET OF BEARING AREA OF CONCRETE ON UNDISTURBED SOIL, OR AS DIRECTED BY THE ENGINEER.
- WATER MAINS WILL NOT BE FULLY PRESSURIZED UNTIL CONCRETE HAS REACHED 7 DAY STRENGTH.
- ALL PIPE WILL BE LAID SO AS THE ENTIRE BARRELL WILL HAVE FULL BEARING ON THE FINE GRADED TRENCH BOTTOM. BELL HOLES SHALL BE CUT FOR EACH BELL AND FIRE HYDRANT.
- ALL FITTINGS SHALL BE MECHANICAL JOINTS UNLESS OTHERWISE DIRECTED.
- HYDRANTS SHALL BE LOCATED NO CLOSER THAN 3 FEET MEASURED FROM THE BACK OF CURB TO THE FACE OF THE STEAMER ON THE FIRE HYDRANT.




STANDARD FIRE HYDRANT ASSEMBLY NTS




BEDDING AND TRENCH FOR REINFORCED CONCRETE PIPE NTS




VIEW A-A




SILT CONTROL FENCE NTS




CONSTRUCTION ENTRANCE/EXIT NTS



STANDARD MANHOLE TIE-IN NTS




PLAN




SECTION A-A

PROPERTY OF SAN ANTONIO WATER SYSTEM SAN ANTONIO, TEXAS	6" TURBINE METER INSTALLATION	APPROVED March 2008	REVISED AUG 2019
		DD-824-09	
		SHEET 2 OF 2	



STORM DRAIN INLET PROTECTION NTS






ADA PARKING SIGN NTS



ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-0123 P
210-829-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1






CLIENT Alamo Colleges	PROJECT NUMBER 230462	
DATE 2024/06/12		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER

C1201


600 S Milman St.
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION

CHECKED BY:
SH & AL
DRAWN BY:
JC



REINFORCING BAR LAP SPICE TABLE (MASONRY), (BEAMS AND COLUMNS), (SLABS AND WALLS). Includes tables for bar size, position, and lap class.

REINFORCING BAR LAP SPICE TABLE (MASONRY), (BEAMS AND COLUMNS), (SLABS AND WALLS). Includes tables for bar size, position, and lap class.




Professional Engineer seal for Shawn J. Franke, project information, and notes/sections & details. Includes contact information for PBK Architects and Lundy & Franke Engineering.



ARCHITECT SAN ANTONIO PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216

ENGINEERING LUNDY & FRANKE 568 HEIMER ROAD San Antonio, Texas 78232


WFCAC Black Box Addition PKG 1 1801 Marlin Luther King Dr. San Antonio, TX 78203



CLIENT: Alamo Colleges, PROJECT NUMBER: 230462, DATE: 2024/05/23

ISSUE FOR CONSTRUCTION BUILDING NUMBER: AB

ISSUE FOR CONSTRUCTION



FOUNDATION PLAN
SCALE: 1/8" = 1'-0"



LA PROJECT NO. 095165-00
LA FILE NO. WFAC-Blackbox Addition Structural R23



ARCHITECT SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-823-9578 F
TX Firm BR 1608

ENGINEERING LUNDY & FRANKE
580 HEIMER ROAD PH 010 979-7900
SAN ANTONIO, TEXAS 78232 FX 010 979-7800
TX FIRM REG. #3888

WFAC Black Box Addition PKG 1
1801 Main, Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION




CLIENT: Alamo Colleges
DATE: 2024/05/23 PROJECT NUMBER: 230462

No.	Description	Date
2	City Comments	06/12/24


ISSUE FOR CONSTRUCTION
BUILDING NUMBER: AB

FOUNDATION FRAMING PLAN


S-201




MECHANICAL YARD FOUNDATION PLAN
SCALE: 1/4" = 1'-0"




5 SECTION
3/4" = 1'-0"



6 SECTION
3/4" = 1'-0"




7 SECTION
3/4" = 1'-0"




CMU LINTEL SCHEDULE

SIZE	CLEAR OPENING		REMARKS
	GREATER THAN	UP TO	
ONE COURSE	-	4'-0"	8" BEARING @ EA. END
TWO COURSE	4'-0"	8'-6"	8" BEARING @ EA. END
THREE COURSE	8'-6"	14'-0"	8" BEARING @ EA. END

- MASONRY WALL REINFORCEMENT:**
- MN-1** PROVIDE GROUTED REINFORCED VERTICAL CELLS AND HORIZONTAL BOND BEAMS AT WALL TOP EDGES, CORNERS, FREE ENDS, WINDOW AND DOOR JAMBS, LINTELS AND OTHER LOCATIONS WHERE SHOWN ON ARCHITECTURAL DRAWINGS. REINFORCE EACH GROUTED CELL AND BOND BEAM WITH 1-#4 BAR CONTINUOUS (REINFORCE LINTELS AS SPECIFIED BELOW).
 - MN-2** BASIC VERTICAL REINFORCEMENT FOR EXTERIOR WALLS SHALL BE #4 @ 32" o.c. (EVERY 4th VERTICAL CELL).
 - MN-3** PROVIDE GROUTED REINFORCED LINTELS WITH 8" BEARING EACH END OF ALL DOORS, WINDOWS, AND OTHER OPENINGS. USE ONE-COURSE LINTELS FOR OPENINGS UP TO 4'-0"; TWO-COURSE LINTELS FOR OPENINGS UP TO 8'-6"; THREE-COURSE LINTELS FOR OPENINGS UP TO 14'-0". REINFORCE EACH COURSE WITH 2-#5 BAR CONTINUOUS.
 - MN-4** PROVIDE MATCHING DOWELS IN FOUNDATION FOR ALL VERTICAL REINFORCEMENT.
 - MN-5** CMU SHALL HAVE A UNIT STRENGTH OF 1,900 PSI. USE TYPE S MORTAR. REINFORCED CMU SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 1100 PSI. GROUT FOR FILLED CELLS SHALL BE MADE OF CEMENT, SAND AND PEA GRAVEL IN APPROXIMATE RATIO OF 1:3:2 AND SHALL HAVE 28-DAY COMPRESSIVE STRENGTH OF 2,500 PSI.
 - MN-6** ANCHOR MASONRY TO STRUCTURE AS SHOWN IN DETAILS. SEE SPECIFICATIONS FOR ORDINARY MASONRY ANCHORS INCLUDING DOVETAIL ANCHOR SLOTS IN ADJACENT CONCRETE MEMBERS.
 - MN-7** LEVEL 1 INSPECTED MASONRY REQUIRES CONTRACTOR TO SUBMIT, AT CONTRACTORS COST, COMPRESSIVE WALL DESIGN STRENGTH (Fm) VERIFIED BY INDEPENDENT TESTING LAB BY PRISM TESTS BEFORE MASONRY CONSTRUCTION BEGINS. PROVIDE UNIT MASONRY STRENGTH, GROUT MIX DESIGN AND MORTAR MIX DESIGN.



4 DETAIL
N.T.S.




1 SECTION
3/4" = 1'-0"

GRADE BEAM SCHEDULE

MARK	W x D*	MAIN REINFORCING	TIES
GB1	12 x 24"	2-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.
GB2	18 x 24"	3-#6 x CONT. TOP & BOTTOM	#3 @ 24" o.c.

- * REF. NOTE FN-4
- FOUNDATION NOTES:**
- FN-1** 5" CONCRETE SLAB REINFORCED W/ #4 @ 12" o.c. EACH WAY IN TOP. SUPPORT AT 4'-0" o.c. EACH WAY WITH CONCRETE BLOCKS OR BRICKS. SUPPORT BOTTOM BEAM REINFORCEMENT AT 4'-0" INTERVALS.
 - FN-2** 15 MIL. POLYOLEFIN VAPOR RETARDER UNLESS NOTES OTHERWISE IN SPECIFICATIONS. AT ALL JOINTS PROVIDE 6" LAPS W/ 4" TAPE.
 - FN-3** COMPACTED SELECT FILL (SEE UF-6 "UNDERFLOOR FILL NOTES").
 - FN-4** ALL BEAM SOFFITS SHALL BEAR 24" MINIMUM INTO NATURAL GRADE OR COMPACTED FILL. ON PERIMETER, INCREASE SCHEDULED BEAM DEPTH AS REQUIRED FOR SOFFIT TO BEAR 24" MINIMUM BELOW FINISH GRADE. REF GEOTECHNICAL REPORT. ALL PERIMETER GRADE BEAMS SHALL BEAR ON LIMESTONE.
 - FN-5** GRADE BEAMS AND SLAB TURNDOWNS SHALL BE FORMED BY WALLS AND SOFFIT OF CAREFULLY SHAPED TRENCH. USE A SMOOTH-MOUTHED BUCKET. IF A TOOTHED BUCKET IS USED, EXCAVATION SHALL BE STOPPED 6" ABOVE FINAL GRADE AND THE REMAINING EXCAVATION ACCOMPLISHED WITH A SMOOTH MOUTHED BUCKET OR BY HAND LABOR TO REMOVE ALL LOOSE SOILS DISTURBED BY THE BUCKET TEETH. WOODFORM EXPOSED FACES TO A DEPTH OF 8" BELOW FINISHED GRADE.
 - FN-6** AT ALL BEAM CORNERS & T-INTERSECTIONS, PROVIDE 4-#7 x 6'-0" CORNER BARS (2-TOP AND 2-BOTTOM).
 - FN-7** TRENCHES SHALL BE VERIFIED FOR SIZE TO MAINTAIN CLEARANCES AROUND REINFORCEMENT PRIOR TO PLACING REINFORCEMENT.
 - FN-8** WHERE BEAM DEPTH EXCEEDS 36", ADD #4 @ 12" o.c. IN EACH FACE OF BEAM.

- UNDERFLOOR FILL NOTES:**
- UF-1** BEFORE ANY CONSTRUCTION IS BEGUN, PERFORM ROUGH GRADING AND CUT SWALES SO THAT GROUNDS WILL DRAIN AWAY FROM THE BUILDING. MAINTAIN DRAINAGE DURING ALL PHASES OF CONSTRUCTION SO THAT STORM WATER WILL BE CONDUCTED AWAY FROM THE BUILDING. KEEP EXCAVATIONS PUMPED FREE OF STORM WATER AT ALL TIMES.
 - UF-2** PRECAUTIONS SHALL BE TAKEN TO PROTECT OPEN EXCAVATIONS FROM EXCESSIVE LOSS OR GAIN IN NATURAL MOISTURE LEVEL PRIOR TO PLACEMENT OF BASE MATERIAL. KEEP MOIST DURING DRY WEATHER AND KEEP STORM WATER PUMPED OUT, INCLUDING NIGHTS AND WEEKENDS, DURING RAINS.
 - UF-3** IN THE AREA OCCUPIED BY THE FOUNDATION AND ALL ADJACENT SIDEWALKS, PLUS 3'-0", REMOVE A MINIMUM OF 7'-0" OF TOPSOIL INCLUDING ALL ORGANIC MATERIALS, ROOTS, ETC. FROM THE SITE. DO NOT USE FOR UNDERFLOOR FILL. REMOVE ADDITIONAL MATERIAL AS NECESSARY TO PROVIDE A MINIMUM OF 7'-0" OF SELECT FILL AS PER UF-6.
 - UF-4** THE RESULTING SURFACE SHALL BE PROOF ROLLED WITH A SUFFICIENTLY HEAVY ROLLER (15 TONS) TO LOCATE AND DENSITY WEAK AND COMPRESSIBLE ZONES. A MINIMUM OF 3 PHASSES OF THE ROLLER IS REQUIRED. ANY SOFT SPOTS SHALL BE REMOVED AND REPLACED WITH COMPACTED SELECT FILL.
 - UF-5** THE ROLLED SUBGRADE SHALL BE SCARIFIED JUST PRIOR TO FILL PLACEMENT TO A MINIMUM DEPTH OF 6" AND RECOMPACTED TO MINIMUM OF 95% OF THE MAXIMUM DENSITY DETERMINED BY ASTM D698 COMPACTION TEST, MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED.
 - UF-6** FOR A DISTANCE OF 3'-0" OUTSIDE OF THE BUILDING LINE AND ALL ADJACENT SIDEWALKS, AND BEGINNING AT THE LOW END, BUILD UP TO THE ELEVATION OF THE BOTTOM OF THE SLAB WITH SELECT CRUSHED STONE FILL CONFORMING TO TxDOT SPECIFICATIONS, ITEM 247, TYPE "A" GRADE 2. A MINIMUM THICKNESS OF 7'-0" IS REQUIRED. NO DIRT FILL SHALL BE USED UNDER THE BUILDING FOUNDATION. SUBMIT WRITTEN CERTIFICATION OF COMPLIANCE WITH TxDOT, ITEM 247 SPECIFICATIONS BY TEST PERFORMED ON FIELD EXAMPLES.
 - UF-7** ALL FILL SHALL BE PLACED IN 8" LOOSE HORIZONTAL LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DENSITY AS DETERMINED BY ASTM D698 COMPACTION TEST. MAINTAINING MOISTURE CONTENT BETWEEN -1 AND +3 PERCENTAGE POINTS UNTIL COVERED. EXCESS FILL AT BUILDING PERIMETER SHALL BE CUT AND GRADED TO COMPLY WITH FINISHED GRADE REQUIREMENTS, AND SHALL BE OVERLAIN WITH A 1'-0" THICK LAYER OF IMPERVIOUS CLAY FOR A MINIMUM DISTANCE OF 5'-0" FROM BUILDING LINE. REFER TO DETAIL 7-7.
 - UF-8** PERFORM ALL EARTH WORK DESCRIBED ABOVE BEFORE TRENCHING FOR GRADE BEAMS OR MECHANICAL LINES.
 - UF-9** REFERENCE GEOTECHNICAL REPORT BY: ? PROJECT NO. ?, DATED ?.



3 DETAIL
N.T.S.




ARCHITECT PBK Architects, Inc.
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-823-5578 F
TX Firm BR 1606



ENGINEERING
588 HEIMER ROAD
SAN ANTONIO, TEXAS 78232
TX FIRM REG. #388

WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT
Alamo Colleges
DATE: 2024/05/23 PROJECT NUMBER: 230462

No.	Description	Date
DRAWING HISTORY		


ISSUE FOR CONSTRUCTION
BUILDING NUMBER: AB

SECTIONS, DETAILS & MECH. YARD FOUNDATION

S-301

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition Structural R23



1 SECTION
1/2" = 1'-0"

EE

W





ARCHITECT	PBK Architects, Inc. 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-5578 F TX Firm BR 1606
ASSOCIATE ARCHITECT	BA ARCHITECTS 1100 W. Loop West San Antonio, TX 78204 210-224-1100 P 210-224-1100 F
CONSULTANT	LANDSCAPE ROSE AND DESIGN 1111 W. Loop West San Antonio, TX 78204 210-224-1100 P 210-224-1100 F
STRUCTURAL	LUNDY & FRANKE ENGINEERING 548 HEIMER ROAD SAN ANTONIO, TEXAS 78232 PH: 210-579-7800 FX: 210-579-7800 TX FIRM REG. #3388
MECHANICAL	
ELECTRICAL	
PLUMBING	
BEAM PROFESSIONALS	
MEASUREMENT	
CONSTRUCTION	



WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION




CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
2024/05/23		
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	

SECTION

S-302

ISSUE FOR CONSTRUCTION



1 SECTION
3/8" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA & ARCHITECTS
CONTRACTOR	CONTRACTOR
DESIGNER	DESIGNER
LANDSCAPE	LANDSCAPE
ROSE AND GROUP	ROSE AND GROUP
STRUCTURAL	STRUCTURAL
LUNDY & FRANKE ENGINEERING	LUNDY & FRANKE ENGINEERING
MEP	MEP
MECHANICAL	MECHANICAL
PROVISION	PROVISION
BEAM PROFESSIONALS	BEAM PROFESSIONALS
MEASUREMENT	MEASUREMENT
210-991-8800	210-991-8800



WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION

S-303

ISSUE FOR CONSTRUCTION

0'
1'



1 SECTION
3/8" = 1'-0"

LA PROJECT NO.: 03/215-00
LA FILE NO.: WFAC-38Blackbox Addition, Structural R23



ARCHITECT **PBK Architects, Inc.**

SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-829-4123 P
210-829-5578 F
TX Firm BR 1606



PROFESSIONAL	DATE
ARCHITECT	12/11/19
ASSOCIATE ARCHITECT	12/11/19
OWNER	
DESIGNER	
TYPING	
LANDSCAPE	
TRUCKING	
STRUCTURAL	
METAL	
MEDIA	
ELECTRICAL	
MECHANICAL	
CIVIL	
SEWER	
WATER	
TRUCKING	
TRUCKING	
TRUCKING	
TRUCKING	



WFAC Black Box Addition PKG 1

1801 Main, Luthor King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges
DATE	2024/05/23
PROJECT NUMBER	230462

No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER **AB**

SECTION
S-304

ISSUE FOR CONSTRUCTION

5'
1'

11.2 11.1

10.1

9.1

REF. PLAN

REF. DTL. 3/S-101

DRILLED FTG.,
REF. PLAN

REINFORCING NOT SHOWN
FOR CLARITY, REF. SHEET
S-401, TYP.

UNDERFLOOR GRADING,
REF. CIVIL DWGS.

2-#6XCNT.
W/ #4 HAIRPINS
@ 24" o.c.

DRILLED FOOTING,
REF. PLAN, TYP.

REINFORCING NOT SHOWN
FOR CLARITY, REF. SHEET
S-401, TYP.

LEVEL 01
0'-0"

GRAVEL
4'-0"

1 SECTION
1/2" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38Blackbox Addition Structural R23




ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1606
ASSOCIATE ARCHITECT	BA & ARCHITECTS 210-820-0123 P 210-829-5578 F TX Firm BR 1606
OWNER	ALAMO COLLEGES
DESIGNER	ALAMO COLLEGES
LANDSCAPE	LANDSCAPE
ROOF AND DRIP	ROOF AND DRIP
STRUCTURAL	LUNDY & FRANKE ENGINEERING
M.E.P.	M.E.P.
MECHANICAL	MECHANICAL
ELECTRICAL	ELECTRICAL
PROFESSIONAL SEAL	PROFESSIONAL SEAL
SCALE	SCALE
DATE	DATE



WFAC Black Box Addition PKG 1

1801 Main St., Lumber King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges
DATE	2024/05/23
PROJECT NUMBER	230462

No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION

S-305

ISSUE FOR CONSTRUCTION

0'
1'



1 SECTION
1/2" = 1'-0"

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-38blackbox Addition, Structural R23




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA ARCHITECTS
OWNER	ALAMO COLLEGES
DESIGNER	ALAMO COLLEGES
LANDSCAPE	ALAMO COLLEGES
ROOF AND DRIP	ALAMO COLLEGES
STRUCTURAL	LUNDY & FRANKE ENGINEERING
M.E.P.	LUNDY & FRANKE ENGINEERING
MECHANICAL	LUNDY & FRANKE ENGINEERING
ELECTRICAL	LUNDY & FRANKE ENGINEERING
PROVISIONS	LUNDY & FRANKE ENGINEERING
BEAM PROFESSIONALS	LUNDY & FRANKE ENGINEERING
MEASUREMENT	LUNDY & FRANKE ENGINEERING
REVISIONS	LUNDY & FRANKE ENGINEERING



WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER AB

SECTION

S-306

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition - Structural R23





ARCHITECT **PBK Architects, Inc.**
 SAN ANTONIO
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-820-4123 P
 210-829-5578 F
 TX Firm BR 1608
 PBK.com

LUNDY & FRANKE
 ENGINEERING
 548 HEIMER ROAD
 SAN ANTONIO, TEXAS 78232
 TX FIRM REG. #3388
 PH: 210-979-7900
 FX: 210-979-7800

WFAC Black Box Addition PKG 1

1801 Main St, Luther King Dr.,
 San Antonio, TX 78203


ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
2024/05/23	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	


SECTIONS

S-307






2 SECTION
3/8" = 1'-0"

NOT USED



1 SECTION
1/2" = 1'-0"

ISSUE FOR CONSTRUCTION





LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-383a30x Addition, Structural R23



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1606
ASSOCIATE ARCHITECT	BA & ARCHITECTS 1210 S. W. Loop SAN ANTONIO, TX 78204
OWNER	ALAMO COLLEGES
DESIGNER	LUNDY & FRANKE ENGINEERING
LANDSCAPE ARCHITECT	LANDSCAPE ARCHITECTS
ROOF AND DRIP	LANDSCAPE ARCHITECTS
STRUCTURAL	LUNDY & FRANKE ENGINEERING
M.E.P.	M.E.P. ENGINEERS
MECHANICAL	M.E.P. ENGINEERS
ELECTRICAL	M.E.P. ENGINEERS
PROFESSIONAL ENGINEER	LUNDY & FRANKE ENGINEERING
REGISTERED PROFESSIONAL ENGINEER	LUNDY & FRANKE ENGINEERING
REGISTERED PROFESSIONAL ENGINEER	LUNDY & FRANKE ENGINEERING
REGISTERED PROFESSIONAL ENGINEER	LUNDY & FRANKE ENGINEERING



WFAC Black Box Addition PKG 1





CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	

SECTIONS
S-308

ISSUE FOR CONSTRUCTION

LA PROJECT NO.: 09316-00
LA FILE NO.: WFAC-Blackbox Addition Structural R23




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-4123 P 210-829-5578 F TX Firm BR 1606	
ASSOCIATE ARCHITECT	BA ARCHITECTS
CONTRACTOR	CONTRACTOR
DESIGNER	DESIGNER
LANDSCAPE	LANDSCAPE
ROOF AND GROUND	ROOF AND GROUND
STRUCTURAL	LUNDY & FRANKE ENGINEERING
MECHANICAL	MECHANICAL
ELECTRICAL	ELECTRICAL
PLUMBING	PLUMBING
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL



WFAC Black Box Addition PKG 1

1801 Main, Luther King Dr.,
San Antonio, TX, 78203
ISSUE FOR CONSTRUCTION




CLIENT	Alamo Colleges	
DATE	2024/05/23	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER	AB	


SECTIONS & DETAILS

S-309


1st FLOOR CONCRETE JOIST SCHEDULE															
MARK	SIZE			MAIN REINFORCING						STIRRUPS			REMARKS		
	W	D	SECT.	SPCG.	TOP BARS		BOTTOM BARS		TOP BARS AT SUPPORT		SIZE	NO. LEGS		SPACING AT EACH END OF JOIST	
					REINF.	TYP.	REINF.	TYP.	REINF.	TYP.	SUPP.				
J1	6	20		6'-0"	2-#6	T2	1-#8	B6	-	-	-	#4	10	11" O.C.	
J2	6	20		6'-0"	1-#8	T3	1-#8	B3	-	-	-	#4	10	11" O.C.	
J3	6	20		6'-0"	1-#6	T1	1-#6	B1	-	-	-	#4	8	11" O.C.	




5 DETAIL TYP. SECT. @ REIN. BM. SCALE: 3/4" = 1'-0"




6 DETAIL TYP. SECT. @ INT. BM. SCALE: 3/4" = 1'-0"




7 DETAIL TYP. ALLOWABLE CONDUIT PLACEMENT SCALE: 3/4" = 1'-0"




1 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"



2 DETAIL TYP. SLAB REINF. @ ACCESS HATCH SCALE: 3/4" = 1'-0"



3 DETAIL TYP. SLAB SECT. @ FLR. DROP SCALE: 3/4" = 1'-0"



4 DETAIL TYP. REINF. @ SLAB DROP SCALE: 3/4" = 1'-0"

- CONCRETE JOIST NOTES:**
- CJ-1 STEEL PAN-JOIST FORMS SHALL BE SPACED SO THAT JOISTS IN ADJACENT SPANS ARE IN EXACT ALIGNMENT UNLESS SHOWN OTHERWISE. NARROWER WIDTH FORMS SHALL BE COORDINATED WITH BASIC SPACING WHERE MAKE-UPS ARE REQUIRED.
 - CJ-2 WHERE STIRRUPS ARE SCHEDULED, (1) 6-LEG LADDER STIRRUP ASSEMBLY WITH VERTICAL LEGS AT 11" O.C. IS THE MINIMUM. IF SCHEDULE CALLS FOR MORE THAN 6 LEGS, USE A COMBINATION OF LADDER STIRRUP ASSEMBLIES TO PROVIDE REQUIRED NUMBER OF LEGS AT SPACING SCHEDULED.
 - CJ-3 JOIST TOP BARS SHALL BE SUPPORTED ON 1" DIA. X 1'-0" SUPPORT BARS PLACED ON 3/4" BAR CHAIRS ACROSS PAN FORMS AT 4'-0" O.C. TIED TO STIRRUPS BEGINNING AT FIRST LEG.
 - CJ-4 BEAM STEEL SHALL HAVE CLEARANCE OF 1-1/2" TO STIRRUPS AT BOTTOM AND SIDES BUT 2-1/2" AT TOP. JOIST STEEL SHALL HAVE CLEARANCE OF 1-1/2". THEREFORE, REINFORCEMENT SHALL BE PLACED IN THE FOLLOWING SEQUENCE:
 1. PLACE ALL BEAM BARS.
 2. PLACE BOTTOM JOIST BARS.
 3. PLACE SUPPORT BARS (NOTE CJ-3).
 4. PLACE TOP JOIST BARS.
 5. PLACE EXTRA SLAB BARS (NOTE CJ-7).
 6. PLACE WELDED WIRE FABRIC.
 - CJ-5 REINFORCE SLAB WITH 4x4-W3.5x3.5 WELDED WIRE FABRIC, LAPPED 1-1/2 MESHES AT SPLICES. DRAPE OVER TOP JOIST BARS AND TIE DOWN SECURELY IN BOTTOM OF SLAB MIDWAY BETWEEN JOISTS. 3/4" OFF BOTTOM WITH BAR CHAIRS AND TIED TO FROM AT 24" O.C. MESH SHALL EXTEND OVER THE ENTIRE WIDTH OF BEAMS.
 - CJ-6 WHERE FLOOR DROPS (DEPRESSIONS) OCCUR, ADJUST PAN FORMS SO THAT SLAB THICKNESS IS MAINTAINED AS SHOWN IN DETAILS.
 - CJ-7 WHERE JOIST RUN PARALLEL TO BEAMS OR WALLS, PROVIDE #3 DOWELS AT 2'-0" O.C. AT EDGE BEAMS ONLY. (SEE DETAIL).
 - CJ-8 UNLESS SPECIFICALLY SHOWN ON FRAMING PLANS, JOISTS SHALL NOT BE INTERRUPTED OR REDUCED IN CROSS SECTIONAL AREAS WITHOUT ENGINEER'S APPROVAL.
 - CJ-9 IF VERTICAL MECHANICAL SLEEVE PROJECTS INTO A JOIST BY MORE THAN 1-1/2", WIDEN JOIST BY USING NEXT SMALLER PAN WIDTH FOR A DISTANCE OF 4'-0" BOTH SIDES OF SLEEVE AND FIELD DRAPE BARS AROUND SLEEVES (NO TORCHING).
 - CJ-10 CONDUITS IN 4-1/2" SLABS SHALL NOT BE LARGER THAN 1" DIAMETER, WHERE CONDUIT IS PARALLEL (OR NEARLY PARALLEL) TO JOIST, DO NOT LOCATE IN CENTER THIRD OF SLAB SPAN.
 - CJ-11 PROVIDE 6" WIDE BRIDGING JOIST WHERE INDICATED "BJ" ON PLAN. REINFORCE WITH 1-#6 CONTINUOUS TOP AND BOTTOM AND ANCHOR INTO TERMINAL BEAMS WITH #6 X 5'-0" CORNER BAR TOP AND BOTTOM.
 - CJ-12 WHERE PARTITIONS RUNNING PARALLEL TO JOISTS ARE DESIGNATED BY THE SYMBOL ON THE FRAMING PLAN, OR NOTED ON ARCHITECTURAL DRAWINGS, ADD #4 X 6'-0" AT 9" O.C. FOR ENTIRE LENGTH OF JOIST SPAN, IN BOTTOM OF SLAB ON 3/4" BAR CHAIRS, RUNNING PERPENDICULAR TO JOISTS FROM JOIST CENTERLINE TO JOIST CENTERLINE.




ARCHITECT PBK Architects, Inc.
 SAN ANTONIO
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-820-0123 P.
 210-829-5578 F.
 TX Firm BR 1606

ENGINEERING
LUNDY & FRANKE
 ENGINEERING
 568 HEIMER ROAD
 SAN ANTONIO, TEXAS 78232
 TX FIRM REG. #3388

WFAC Black Box Addition PKG 1

ALAMO COLLEGES
 ST. PHILIP'S COLLEGE



SHAWN J. FRANKE
 82639
 LICENSED PROFESSIONAL ENGINEER


CLIENT: Alamo Colleges
 DATE: 2024/05/23
 PROJECT NUMBER: 230462

No.	Description	Date

ISSUE FOR CONSTRUCTION
 BUILDING NUMBER: AB

CONC. JOIST SCHED,
 NOTES & DETAILS

ISSUE FOR CONSTRUCTION



GENERAL SITE DEMOLITION NOTES

- DEMOLITION PLANS INDICATE SOME OF THE SCOPE OF WORK INVOLVED FOR THE DEMOLITION PHASE OF THIS PROJECT. CONTRACTOR SHALL REVIEW ALL SHEETS FOR ADDITIONAL DEMOLITION SCOPE.
- CONTRACTOR SHALL VERIFY EXISTING SITE AND BUILDING CONDITIONS AND DIMENSIONS IN THE FIELD PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY DISCREPANCIES IN WRITING.
- CONTRACTOR SHALL NOTIFY ARCHITECT AND OWNER OF ANY POSSIBLE ASBESTOS CONTAINING MATERIALS DISCOVERED BEFORE PROCEEDING WITH WORK. PROTECT INTERIOR CONSTRUCTION TO REMAIN DURING DEMOLITION AND CONSTRUCTION.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS BEFORE COMMENCING WORK.
- AFTER AWARD OF THE CONTRACT, CHANGE ORDER REQUESTS FOR ADDITIONAL MONEY WILL NOT BE APPROVED IF THE WORK COULD HAVE BEEN ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR.
- CONTRACTOR SHALL NOT SCALE DRAWINGS.
- CONTRACTOR SHALL PROVIDE ALL NECESSARY TEMPORARY SHORING, TEMPORARY BRACING, AND OR TEMPORARY SUPPORTS AS REQUIRED TO MAINTAIN STRUCTURAL INTEGRITY OF EXISTING STRUCTURE TO REMAIN AND OR EXISTING BUILDING ELEMENTS TO REMAIN.
- CONTRACTOR IS TO VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES PRIOR TO DEMOLITION ACTIVITIES AND WORK.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS REGULARLY AS NECESSARY TO ELIMINATED INTERFERENCE WITH ROADS, STREET, WALKS, AND ALL OTHER ADJACENT FACILITIES.
- CONTRACTOR SHALL REMOVE TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.
- CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTION OF TEMPORARY DUST AND OR SOUND PARTITION BETWEEN CONSTRUCTION AREA AND AREAS NOT IN SCOPE AS NECESSARY. DEMOLITION ACTIVITIES SHALL BE PERFORMED SO AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY AND OCCUPANTS (I.E. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST).
- CONTRACTOR SHALL REPAIR, REPLACE, OR PATCH EXISTING BUILDINGS, DRIVEWAYS, SIDEWALKS, CANOPIES, AND OR PARKING AREAS DAMAGED, MODIFIED, AND OR DISTURBED BY DEMOLITION WORK AT NO COST TO THE OWNER.
- ALL EXISTING EQUIPMENT THAT REMAINS SHALL BE PROTECTED DURING DEMOLITION AND OR CONSTRUCTION TO PREVENT DAMAGE. ANY DAMAGE TO REMAINING EXISTING EQUIPMENT SUSTAINED DURING DEMOLITION AND OR CONSTRUCTION SHALL BE EQUIVALENTLY REPLACED OR EQUIVALENTLY REPAIRED AT NO COST TO THE OWNER.
- CONTRACTOR SHALL PROVIDE TRAFFIC HANDLING MEASURES TO PROTECT THE GENERAL PUBLIC AT ALL TIMES, AS NECESSARY AND AS REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- DO NOT INTERRUPT EXISTING UTILITIES, EXCEPT WHEN AUTHORIZED IN WRITING BY AUTHORITIES HAVING JURISDICTION. PROVIDE TEMPORARY SERVICES DURING INTERRUPTIONS TO EXISTING UTILITIES AS ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION.
- WHEN UTILITY SERVICES ARE REQUIRED TO BE REMOVED, RELOCATED, OR ABANDONED, PROVIDE BYPASS CONNECTIONS TO MAINTAIN CONTINUITY OF SERVICE BEFORE PROCEEDING WITH DEMOLITION.
- CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES INCLUDING BUT NOT LIMITED TO THE FOLLOWING: ELECTRIC, GAS, WATER, TELEPHONE, STORM SEWER, AND SANITARY SEWER FOR FIELD LOCATION OF ALL UNDERGROUND AND OVERHEAD UTILITY LINES. PRIOR TO COMMENCEMENT OF ANY DEMOLITION WORK, CONTRACTOR SHALL IDENTIFY ALL ELECTRICAL CIRCUITS SERVICING THE AREA INVOLVED WITH THIS DEMOLITION. THOSE CIRCUITS SHALL THEN BE LOCKED OUT AND TAGGED OUT IF THEY DO NOT SERVICE ANY OF THE REMAINING BUILDING. THOSE CIRCUITS WHICH ARE IDENTIFIED TO SERVICE BOTH THE AREA TO BE DEMOLISHED AND THE REMAINING BUILDING SHALL BE SPLIT SO AS TO KILL ALL ELECTRICAL POWER TO THE AREA TO BE DEMOLISHED WHILE MAINTAINING POWER TO THE REMAINDER OF THE BUILDING.
- CONTRACTOR SHALL RELOCATE UTILITIES AND EQUIPMENT AS REQUIRED TO ACCOMMODATE NEW HVAC, ELECTRICAL, PLUMBING, AND TECHNOLOGY REQUIREMENTS FOR NEW WORK.
- PROTECT EXISTING SITE ELEMENTS AND EXISTING LANDSCAPING TO REMAIN. PROTECTION SHALL INCLUDE BUT NOT BE LIMITED TO EXISTING TREES AND OTHER EXISTING VEGETATION INDICATED TO REMAIN IN PLACE AGAINST UNNECESSARY CUTTING, BREAKING, OR SKINNING OF ROOTS, SKINNING OR BRUISING OF BARK, SMOTHERING OF TREES BY STOCKPILING CONSTRUCTION MATERIAL OR EXCAVATED MATERIAL WITHIN DRIP LINES.
- CONTRACTOR SHALL REGRADE AND HYDROMULCH AREAS AFFECTED BY DEMOLITION.
- OWNER HAS RIGHT OF FIRST REFUSAL OF ALL ITEMS REMOVED AS PART OF THE SCOPE OF WORK, WHETHER IDENTIFIED AS SALVAGE OR NOT.
- NOTIFY THE BUILDING OWNER OF ANY MATERIALS, FIXTURES, ETC. TO BE REMOVED THAT ARE DESIRED SALVAGEABLE. TURN OVER ANY REQUESTED ITEMS TO THE BUILDING OWNER IN GOOD AND CLEAN CONDITION.
- ALL FURNITURE WILL BE REMOVED OR RELOCATED BY THE OWNER AS NECESSARY PRIOR TO THE DEMOLITION WORK OF THIS PROJECT. CONTRACTOR SHALL COORDINATE WITH OWNER AS REQUIRED.




ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608	
ARCHITECT	PBK Architects, Inc.
DESIGNER	PKB Architects, Inc.
LANDSCAPE	PKB Architects, Inc.
ENGINEER	PKB Architects, Inc.
MECHANICAL	PKB Architects, Inc.
ELECTRICAL	PKB Architects, Inc.
PLUMBING	PKB Architects, Inc.
CONSTRUCTION	PKB Architects, Inc.
MEASUREMENT	PKB Architects, Inc.
MARKING	PKB Architects, Inc.
TRACING	PKB Architects, Inc.

WFAC Black Box Addition PKG 1

1801 Main Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date

SITE DEMOLITION PLAN LEGEND

- EXISTING BUILDING
- DEMO ENTIRE FACILITY (FOUNDATION, STRUCTURE, WALLS, ROOFS)
- DEMO CHAINLINK FENCE
- DEMO ORNAMENTAL FENCE

06 DEMOLITION SITE PLAN
1" = 20'-0"


ISSUE FOR CONSTRUCTION

BUILDING NUMBER 1

DEMOLITION ARCHITECTURAL SITE PLAN

ASD101

ISSUE FOR CONSTRUCTION



GENERAL ARCH SITE PLAN NOTES

- 1. REFER TO CIVIL DOCUMENTS.
2. COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL, LANDSCAPE, AND OR STRUCTURAL DOCUMENTS.
3. PROVIDE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 1% MINIMUM, 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS, INCLUDING BUT NOT LIMITED TO SIDEWALKS, PATIOS, STAIRS, PAVING, U.N.O.
4. PROVIDE AND INSTALL POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 5% FOR A HORIZONTAL DISTANCE OF 10 FEET AT ALL EXTERIOR NON-PAVED AREAS U.N.O.
5. REFER TO CIVIL DOCUMENTS FOR CONCRETE SIDEWALK EXPANSION JOINTS AND CONCRETE SIDEWALK CONTROL JOINTS.
6. VERIFY AND CONFIRM ALL JOINT LAYOUTS AT ALL CONCRETE SIDEWALKS WITH ARCHITECT PRIOR TO POURING OF CONCRETE.
7. PROVIDE AND INSTALL CONCRETE SIDEWALK EXPANSION JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT 50 FEET ON-CENTER MAX. U.N.O.
8. PROVIDE AND INSTALL CONCRETE SIDEWALK CONTROL JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT DISTANCES EQUIVALENT TO SIDEWALK WIDTH, BUT NOT TO EXCEED 10 FEET ON-CENTER MAX.
9. VERIFY ALL SITE SIGNAGE LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION OF SITE SIGNAGE.



Table with project details: ARCHITECT (PBK Architects, Inc.), SAN ANTONIO, 601 N.W. Loop 410, Suite 400, San Antonio, TX 78216.

WFAC Black Box Addition PKG 1
1801 Martin Luther King Dr., San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



BRICK QUANTITY TAKEOFF

LISTED AREAS ARE ACTUAL SQ. FT. TAKE-OFF FORM FROM THE PACKAGE 2 60% CD SET. GC TO ORDER OVERAGE/WASTE AS REQUIRED.
ORANGE BRICK - 12,200 SF
WHITE BRICK - 2,275 SF
IF SPANDREL REPLACEMENT FOR BRICK VE OPTION IS SELECTED ADDED BRICK COUNT
ORANGE BRICK - 490 SF
WHITE BRICK - 155 SF

ARCH SITE PLAN LEGEND

Legend table with symbols and descriptions: EXISTING BUILDING, NOT IN SCOPE, NEW BUILDING / ADDITION, GRASS, SIDEWALK, TOP CAST CONCRETE, RE: LANDSCAPE, SALT FINISH CONCRETE, RE: LANDSCAPE.












Table with drawing history: CLIENT (Alamo Colleges), DATE (2024/06/14), PROJECT NUMBER (230462), DRAWING HISTORY table.

ISSUE FOR CONSTRUCTION

ARCHITECTURAL SITE PLAN

AS100



GENERAL ARCH SITE PLAN NOTES

- REFER TO CIVIL DOCUMENTS.
- COORDINATE ALL SPOT ELEVATIONS AND DIMENSIONS WITH CIVIL, LANDSCAPE, AND/OR STRUCTURAL DOCUMENTS.
- PROVIDE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 1% MINIMUM, 2% MAXIMUM AT ALL EXTERIOR PAVED PEDESTRIAN AREAS, INCLUDING BUT NOT LIMITED TO SIDEWALKS, PATIOS, STAIRS, PAVING, U.N.O.
- PROVIDE AND INSTALL POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS OF 5% FOR A HORIZONTAL DISTANCE OF 10 FEET AT ALL EXTERIOR NON-PAVED AREAS U.N.O.
- REFER TO CIVIL DOCUMENTS FOR CONCRETE SIDEWALK EXPANSION JOINTS AND CONCRETE SIDEWALK CONTROL JOINTS.
- VERIFY AND CONFIRM ALL JOINT LAYOUTS AT ALL CONCRETE SIDEWALKS WITH ARCHITECT PRIOR TO POURING OF CONCRETE.
- PROVIDE AND INSTALL CONCRETE SIDEWALK EXPANSION JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT 50 FEET ON-CENTER MAX. U.N.O.
- PROVIDE AND INSTALL CONCRETE SIDEWALK CONTROL JOINTS AT AREAS NOT SPECIFICALLY INDICATED AT DISTANCES EQUIVALENT TO SIDEWALK WIDTH, BUT NOT TO EXCEED 10 FEET ON-CENTER MAX.
- VERIFY ALL SITE SIGNAGE LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION OF SITE SIGNAGE.

KEYNOTE LEGEND

NUMBER	DESCRIPTION
04 05 00 CDP	CAVITY DRAINAGE MATERIAL
04 05 00 TIE	TIE SYSTEM
04 05 00 WWV	WICKING WEEP
04 20 00 BK1	BRICK TYPE 1 - FIELD
04 20 00 BK2	BRICK TYPE 2 - WHITE ACCENT
04 20 00 CBB	CMU BOND BEAM
04 20 00 CUB (R)	8" CMU - RUNNING BOND

ARCH SITE PLAN LEGEND

[Solid Grey]	EXISTING BUILDING
[Hatched]	NOT IN SCOPE
[Blue Hatched]	NEW BUILDING / ADDITION
[Green]	GRASS
[Stippled]	SIDEWALK
[Light Grey]	TOP CAST CONCRETE, RE. LANDSCAPE
[White]	SALT FINISH CONCRETE, RE. LANDSCAPE




ARCHITECT: **PBK Architects, Inc.**
SAN ANTONIO
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-820-0578 F
TX Firm BR 1608

WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203

ISSUE FOR CONSTRUCTION




CLIENT: Alamo Colleges
DATE: 2024/06/14
PROJECT NUMBER: 230462

No.	Description	Date
1	AS1 #1 - CITY & OWNER COMMENTS	6-14-2024


ISSUE FOR CONSTRUCTION
BUILDING NUMBER: 1

ARCHITECTURAL ENLARGED SITE PLANS


AS401




30 UNDERGROUND SUMP PUMP DETAIL
1/4" = 1'-0"



29 AREAWAY DETAIL
3/4" = 1'-0"



18 UNDERFLOOR ACCESS DOOR
3/4" = 1'-0"




06 CRAWLSPACE
1/8" = 1'-0"

GENERAL ARCH PLAN NOTES

- DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE. CONTACT ARCH IF CLARIFICATION IS NECESSARY IN ORDER TO DETERMINE THE INTENT OF THE CONTRACT DOCUMENTS.
- DRAWINGS NOTED AS "N.T.S." OR "NTS" ARE NOT TO SCALE.
- ALL DIMENSIONS ARE TO STRUCTURAL COLUMN LINES OR THE SURFACE OF PARTITION ASSEMBLY U.N.O.
- FIELD VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE COMMENCING WORK. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH AFFECTED WORK.
- NOTES OR DIMENSIONS NOTED AS "TYPICAL" OR "TYP." OR "TYP" SHALL APPLY TO CONDITIONS THAT ARE THE SAME, OR SIMILAR.
- DIMENSIONS NOTED AS "FIELD VERIFY" OR "V.I.F." OR "V.I.P." SHALL BE MEASURED AND CONFIRMED AT THE PROJECT SITE BY THE CONTRACTOR AND REVIEWED WITH THE ARCH. BEFORE INCORPORATING INTO THE WORK.
- DIMENSIONS NOTED AS "CLEAR" OR "CLEAR INSIDE" OR "CLR" REQUIRE SPECIFIC COORDINATION AMONG DISCIPLINES AND OR MANUFACTURERS.
- REFER TO PARTITION TYPES ON A-800 SERIES SHEETS.
- ALL INTERIOR PARTITIONS THIS SHEET, EXCEPT FOR FURR-OUT PARTITIONS, SHALL BE PARTITION TYPE _SR_ U.N.O.
- ALL INTERIOR FURR-OUT PARTITIONS THIS SHEET SHALL BE PARTITION TYPE _F3_ U.N.O.
- ADJOIN FINISHED FACE OF WALLS WHERE WALL PARTITIONS OF DIFFERING THICKNESS ABUT AND OR ADJOIN IN THE SAME PLANE.
- PROVIDE AND INSTALL CONTINUOUS REVEAL TRIM AT JOINT WHERE GYPSUM BOARD WALL PARTITIONS ABUT AND OR ADJOIN MASONRY WALL PARTITIONS IN THE SAME PLANE.
- ALL INTERIOR CMU OUTSIDE CORNERS SHALL HAVE BULLNOSE U.N.O.
- ALL DOORS SHALL BE SET 4 INCHES OFF THE ADJACENT PERPENDICULAR WALL ON THE HINGE SIDE OF THE DOOR U.N.O. NOTIFY ARCH. OF ANY DOOR-RELATED CONFLICTS, INCLUDING BUT NOT LIMITED TO CONFLICTS CONCERNING ACCESSIBILITY STANDARDS.
- ALL DOOR THRESHOLDS AT ALL EXTERIOR DOORS SHALL BE SET IN FULL BED OF SEALANT.
- COORDINATE ALL ROOF DRAIN LEADER LOCATIONS WITH FLOOR PLAN PRIOR TO FLOOR SLAB CONSTRUCTION.
- ALL FLOOR SLOPES TO FLOOR DRAINS SHALL NOT EXCEED 1:48.
- PROVIDE AND INSTALL SELF-LEVELING UNDERLAYMENT WHERE UNEVEN FLOOR SLAB EXISTS PRIOR TO INSTALLATION OF FLOOR FINISHES.
- COORDINATE HOUSEKEEPING PAD LOCATIONS AND DIMENSIONS WITH EQUIPMENT TO BE INSTALLED.
- ALL FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS U.N.O.
- ALL FLOOR FINISH MATERIAL CHANGES SHALL HAVE REDUCER STRIPS.
- ALL REQUIRED ACCESSIBLE CLEARANCES FOR ALL ITEMS, INCLUDING BUT NOT LIMITED TO ALL COUNTER TOPS, ALL PLUMBING FIXTURES, ALL DRINKING FOUNTAINS, ALL ELECTRIC WATER COOLERS, ALL LAVATORIES, ALL URINALS, ALL TOILETS SHALL BE STRICTLY ENFORCED.
- APPLY BITUMINOUS COATING TO ALL CONCEALED STRUCTURAL STEEL MEMBERS AT ALL EXTERIOR CANOPY LOCATIONS.
- REFER TO OTHER DISCIPLINE DOCUMENTS FOR ADDITIONAL SCOPE OF WORK.


FLOOR FINISH LEGEND



ARCHITECT PBK Architects, Inc.
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1608

ARCHITECT BA & ARCHITECTS
 1801 Marlin Luther King Dr.,
 San Antonio, TX 78203

ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
2024/06/14		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER 1

CRAWLSPACE FLOOR PLAN - COMPOSITE

A-811 FOR BLUEBAM LABELING CORR.

ISSUE FOR CONSTRUCTION

File Path: AutodesK Doss://Alamo CS_230462_Ar Philip College WEB Add/230462 WFAC - Blackbox Addition - A23.rvt
CHECKED BY:
Checked By:
DRAWN BY:
Author:
Plot Stamp:
6/13/2024 4:32:51 PM

DOOR SCHEDULE PANEL AND FRAME TYPES


DOOR SCHEDULE - PKG1											
MARK	ROOM NAME	PHASE	PAIR	PANEL				FRAME			
				WIDTH	HEIGHT	TYPE	MATERIAL	GLASS	TYPE	FINISH	
LEVEL 01											
159	BLACKBOX	New Construction	PAIR	14' - 0"	12' - 0"	SCU		N	00UE	PAINTED STEEL	

MATERIALS	
AL - ALUMINUM	VL - VINYL
HM - HOLLOW METAL	PL - PLASTIC LAMINATE
HG - HOLLOW METAL GALV	WS - WOOD, SOLID CORE
HS - HM 24 GA. STEEL	WH - WOOD, HOLLOW CORE
SS - STAINLESS STEEL	PTDF - PAINTED TYPE
REMARKS LEGEND	
1. WITH EGRESS DEVICE	
2. MAGNETIC DOOR HOLDER	
3. FIRE DOOR	
4. ELEVATOR MACHINE ROOM DOORS	
5. ELECTRICAL ROOM DOORS	
6. KICK PLATE ON BOTH SIDES	
7. ACCESS PANEL DOOR	
8. WITH CLOSER	



ARCHITECT		PBK Architects, Inc.	
SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1808			
ARCHITECT	ALAMO COLLEGES	PROJECT NUMBER	230462
DATE	2024/06/14	ISSUE FOR CONSTRUCTION	1

WFAC Black Box Addition PKG 1





DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION

BUILDING NUMBER **1**

**DOOR SCHEDULE
PANEL AND FRAME
TYPES**


A-811



DOOR FRAME CONFIGURATIONS PKG 1
1/4" = 1'-0"

DOOR PANEL TYPES PKG 1
1/4" = 1'-0"

ISSUE FOR CONSTRUCTION



KEYNOTES ALL

- M1 4" CHWS/R PIPING ROUTED FROM EXISTING CAMPUS LOOP VAULT BELOW FLOOR SLAB. REFER TO M-101D FOR CONTINUATION
- M2 APPROXIMATE LOCATION OF EXISTING CHILLED WATER LOOP VAULT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P43

1 MECHANICAL AND PLUMBING SITE PLAN
SCALE: 1" = 20'-0"

File Path: AutodesK Dcs://Name CS_230462_A1 Philip College WBB AddP23 WFAC- Blackbox Addition -A03.rvt
CHECKED BY: [Blank]
Checked By: [Blank]
DRAWN BY: [Blank]
Author: [Blank]
Plot Stamp: [Blank]
6/12/2024 4:05:39 PM





ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	BLA ARCHITECTS 200 1311 S. BRASS LANDSCAPE 1311 S. BRASS LUNNEY & FRANKS ENGINEERING 1311 S. BRASS 1311 S. BRASS 1311 S. BRASS 1311 S. BRASS 1311 S. BRASS 1311 S. BRASS 1311 S. BRASS



WFAC Black Box Addition PKG 1

1801 Marlin Luther King Dr.,
San Antonio, TX 78203
ISSUE FOR CONSTRUCTION



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

MECHANICAL AND PLUMBING SITE PLAN


MPS-101

ISSUE FOR CONSTRUCTION

File Path: Autodesk Docs://Alamo CS_230462_Al Philip College WBB Add#E23 WFAC - Blackbox Addition - A23.rvt

CHECKED BY:
Checker
DRAWN BY:
Author
Plot Stamp:
6/13/2024 12:25:09 PM

5
1



DEMO SITE PLAN GENERAL NOTES:

- COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

SITE PLAN KEYED NOTES:



- EXISTING ELECTRICAL MANHOLE.
- EXISTING ELECTRICAL MANHOLE SHALL BE DEMOLISHED AND RELOCATED.
- EXISTING UNDERGROUND ELECTRICAL DUGBANK WITH 4 EXISTING CONDUITS TO BE REROUTED FOR NEW BLACK BOX EXPANSION.
- CONTRACTOR TO VERIFY NEW CONSTRUCTIONS DOES NOT OVERLAP EXISTING PARKING LOT LIGHTING. IF NEW CONSTRUCTIONS OVERLAPS EXISTING FEEDER FOR PARKING LOT LIGHTING, EXISTING FEEDERS FOR SITE LIGHTING SHALL BE RELOCATED.
- EXISTING CONDENSING UNIT SHALL BE RELOCATED. DISCONNECT AND CONDUCTORS SHALL BE REROUTED. UTILIZE EXISTING CIRCUIT. COORDINATE EXACT LOCATION WITH MECHANICAL DRAWINGS.
- EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
- EXISTING CONDUITS FROM DP-6 TO WATSON'S FINE ARTS BUILDING SHALL BE RELOCATED TO ACCOMMODATE NEW BUILDING. CONTRACTOR SHALL VERIFY PATH WAY AND RELOCATED CONDUITS AND CONDUCTORS TO NEW AVAILABLE LOCATION WITHOUT IMPEDE ANY OTHER SERVICES.
- EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
- EXISTING PARKING LOT FIXTURES SHALL BE DEMOLISHED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.
- EXISTING PEDESTRIAN LOT FIXTURES SHALL BE RELOCATED. CONTRACTOR SHALL PRESERVE CIRCUIT RUN FOR ANY EXISTING FIXTURES REMAINING OR TIED TO DEMOLISHED FIXTURES.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-5578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-224-1000
CONSULTANT	LANDSCAPE TERRACE GROUP 1111 W. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-224-1000
MECHANICAL ENGINEER	LUNY & FRANK ENGINEERING 1111 W. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-224-1000
ELECTRICAL ENGINEER	LEAF ENGINEERS 1801 MAIN LUTHER KING DR. SAN ANTONIO, TX 78203 210-224-1000



WFAC Black Box Addition PKG 1




CLIENT		
Alamo Colleges	PROJECT NUMBER	
DATE	230462	
06/14/2024		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

DEMO SITE POWER PLAN

EDS-101



- ELECTRICAL ONE-LINE DIAGRAM NOTES:**
- # INDICATES GENERAL NOTE.
 - Ⓢ INDICATES KEYED NOTE.
 - 1. REFER TO RISER DIAGRAM FOR FEEDER WIRE / CONDUIT SIZES AND FOR ALL FEEDER SIZES NOT SHOWN ON THIS SHEET.
 - 2. 1 #3/0 COPPER GROUND CONDUCTOR IN 1" CONDUIT TO MAIN INCOMING METAL WATER PIPE, TO MAKE GROUNDING ELECTRODE AND TO BUILDING GROUND.
 - 3. NEC 285 SURGE PROTECTIVE DEVICE. RE: DIVISION 26 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 - 4. ST. PHILLIPS COLLEGE PROVIDED UTILITY TRANSFORMER. CONTRACTOR SHALL COORDINATE WITH ST. PHILLIPS COLLEGE FOR TRANSFORMER NOMENCLATURE.






ARCHITECT	PBK Architects, Inc.
601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-820-0123 P 210-829-9578 F TX Firm BR 1608	
ASSOCIATE ARCHITECT	B&A ARCHITECTS
DESIGNER	DESIGNER
LANDSCAPE	LANDSCAPE
SUBMITTAL GROUP	SUBMITTAL GROUP
MECHANICAL	MECHANICAL
ELECTRICAL	ELECTRICAL
PLUMBING	PLUMBING
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL
MECHANICAL	MECHANICAL



WFAC Black Box Addition PKG 1

1801 Mathis Luther King Dr.,
San Antonio, TX 78203



CLIENT	Alamo Colleges	
DATE	06/14/2024	PROJECT NUMBER
		230462
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

ELECTRICAL ONE-LINE DIAGRAM

GENERAL ELECTRICAL NOTES

- 1. UNLESS SPECIFICALLY INDICATED ON THE DRAWINGS OR OTHERWISE INSTRUCTED BY THE ARCHITECT, ELECTRICAL OUTLETS SHALL HAVE THE FOLLOWING MOUNTING HEIGHTS. DIMENSIONS ARE TO CENTER OF BOX UNLESS OTHERWISE NOTED. WALL SWITCHES 15" AFF TO BOTTOM OF BOX...

AFF = ABOVE FINISHED FLOOR AFG = ABOVE FINISHED GRADE

- 2. UNLESS SPECIFICALLY INDICATED ON THE ELECTRICAL DRAWINGS, OUTLETS LOCATED AT COUNTERS AND CABINETS SHALL BE MOUNTED AS SHOWN ON ARCHITECTURAL DETAILS AND ELEVATIONS, OR AS DIRECTED BY ARCHITECT.

- 3. COORDINATE MOUNTING HEIGHTS AND DETAILS OF ALL OUTLETS (POWER, SIGNAL, ETC.) WITH ARCHITECTURAL CASEWORK DRAWINGS PRIOR TO DIVISION 26 ROUGH-IN. PROVIDE COORDINATION DRAWINGS IN ACCORDANCE WITH DIVISION 26 SPECIFICATIONS WHERE CONFLICTS EXIST.

- 4. REFER TO MECHANICAL DRAWINGS FOR EXACT LOCATION OF ALL HVAC AND PLUMBING EQUIPMENT. CIRCUITING A. BRANCH CIRCUITING IS SCHEMATIC IN NATURE AND IS INTENDED TO INDICATE CIRCUIT LOADING AND CONTROL...

LIGHTING FIXTURE NOTES

KEY TO NOTE PREFIXES: "G" NOTES ARE "GENERAL" LIGHTING NOTES THAT APPLY TO THE ENTIRE PROJECT. "S" NOTES ARE "SCHEDULE" NOTES THAT APPLY TO SPECIFIC LUMINAIRES.

- G.1 REFER TO ARCHITECTURAL REFLECTED CEILING PLANS, ELEVATIONS, SECTIONS, AND DETAILS FOR THE EXACT LOCATION OF ALL LUMINAIRES ARCHITECTURAL PLANS SHALL GOVERN FOR LOCATION AND LAYOUT.

GENERAL ELECTRICAL REMODEL NOTES

- 1. UNLESS SPECIFICALLY INDICATED ON THE DRAWINGS OR OTHERWISE INSTRUCTED BY THE ARCHITECT, ELECTRICAL OUTLETS SHALL HAVE THE FOLLOWING MOUNTING HEIGHTS. DIMENSIONS ARE TO CENTER OF BOX UNLESS OTHERWISE NOTED. WALL SWITCHES 15" AFF TO BOTTOM OF BOX...

AFF = ABOVE FINISHED FLOOR AFG = ABOVE FINISHED GRADE

- 2. UNLESS SPECIFICALLY INDICATED ON THE ELECTRICAL DRAWINGS, OUTLETS LOCATED AT COUNTERS AND CABINETS SHALL BE MOUNTED AS SHOWN ON ARCHITECTURAL DETAILS AND ELEVATIONS, OR AS DIRECTED BY ARCHITECT.

- 3. COORDINATE MOUNTING HEIGHTS AND DETAILS OF ALL OUTLETS (POWER, SIGNAL, ETC.) WITH ARCHITECTURAL CASEWORK DRAWINGS PRIOR TO DIVISION 26 ROUGH-IN. PROVIDE COORDINATION DRAWINGS IN ACCORDANCE WITH DIVISION 26 SPECIFICATIONS WHERE CONFLICTS EXIST.

- 4. REFER TO MECHANICAL DRAWINGS FOR EXACT LOCATION OF ALL HVAC AND PLUMBING EQUIPMENT. CIRCUITING A. BRANCH CIRCUITING IS SCHEMATIC IN NATURE AND IS INTENDED TO INDICATE CIRCUIT LOADING AND CONTROL...

LIGHTING FIXTURE NOTES

KEY TO NOTE PREFIXES: "G" NOTES ARE "GENERAL" LIGHTING NOTES THAT APPLY TO THE ENTIRE PROJECT. "S" NOTES ARE "SCHEDULE" NOTES THAT APPLY TO SPECIFIC LUMINAIRES.

- G.1 REFER TO ARCHITECTURAL REFLECTED CEILING PLANS, ELEVATIONS, SECTIONS, AND DETAILS FOR THE EXACT LOCATION OF ALL LUMINAIRES ARCHITECTURAL PLANS SHALL GOVERN FOR LOCATION AND LAYOUT.

CONTACTOR SCHEDULE table with columns: DESIGNATION, CIRCUITS SERVED, CONTACT AMPS, N.O. POLES, COIL VOLTS, CONTROL, SUPPLY CKT., REMARKS

1 PROVIDE ASCO ACCESSORY 47 SOLID STATE TWO-WIRE CONTROL INTERFACE MODULE.

ELECTRICAL SYMBOL LEGEND

- 1. EVERY SYMBOL SHOWN ON LEGEND MAY NOT APPEAR ON DRAWINGS. 2. DASHED ELECTRICAL EQUIPMENT GENERALLY INDICATES EXISTING EQUIPMENT. 3. LONG-SHORT-SHORT-LONG DASHING GENERALLY INDICATES MATCH LINE OR DEFINES AREA FOR SPECIAL NOTE.

CIRCUIT RELATED: LIGHTING OR POWER CIRCUIT(S). ARROW INDICATES HOME RUN. LONGER TICK(S) INDICATE NEUTRAL WIRE(S), SHORTER STRAIGHT TICK(S) INDICATE PHASE WIRE(S)...

LIGHTING: LED LIGHTING FIXTURE. LETTER INDICATES TYPE. SMALL LETTER INDICATES SWITCH CONTROL. NUMBER INDICATES CIRCUIT. CROSS HATCHING INDICATES FIXTURE ON EMERGENCY SYSTEM...

CONTROL: SWITCH. SMALL LETTER INDICATES FIXTURES CONTROLLED. "PI" INDICATES PILOT LIGHT. "WP" INDICATES WEATHERPROOF. "K" INDICATES KEY OPERATED. "MO" INDICATES SPDT MOMENTARY CONTACT...

POWER OUTLETS: 20A-125V DUPLEX RECEPTACLE. 20A-125V GROUND FAULT CIRCUIT INTERRUPTER RECEPTACLE. "WP" INDICATES WEATHER PROOF DEVICE...

TELEPHONE/DATA: FLUSH FLOOR TELEPHONE OUTLET WITH CARPET FLANGE WHERE APPLICABLE. WALL COMMUNICATIONS OR DATA OUTLET. REFER TO 'TS' SERIES SHEETS FOR EXACT BOX / CONDUIT REQUIREMENTS...


EQUIPMENT: "42" A NOTATION INDICATING THE MOUNTING HEIGHT OF A DEVICE AS MEASURED FROM FINISHED FLOOR OR GRADE TO CENTER LINE OF DEVICE. MOTOR. DISCONNECT SWITCH...




ARCHITECT table listing project details: SAN ANTONIO, 601 N.W. Loop 410, Suite 400, San Antonio, TX 78216



WFAC Black Box Addition PKG 1. 1801 Main Luther King Dr., San Antonio, TX, 78203. ISSUE FOR CONSTRUCTION




KEY PLAN. NORTH, PLAN, TRUE. Includes a site plan diagram.




CLIENT table: Alamo Colleges, DATE 06/14/2024, PROJECT NUMBER 230462

DRAWING HISTORY table with columns: No., Description, Date


ISSUE FOR CONSTRUCTION. BUILDING NUMBER 1. ELECTRICAL SYMBOL LEGEND AND CONTACTOR SCHEDULE. E-601




4 ELECTRIC SERVICE GROUNDING DETAIL
NOT TO SCALE




8 GROUNDING COMPRESSION CONNECTIONS
NOT TO SCALE



3 EQUIPMENT ANCHOR DETAIL
NOT TO SCALE




6 GROUND BUS DETAIL
NOT TO SCALE




7 GROUND ROD ASSEMBLY
NOT TO SCALE

KEYED NOTES:


1. REQUIRES BURNDY7750 PRESS WITH U99 FOR INSTALLATION.
2. CRIMP CONNECTOR, #2 TO 250 KCMIL TO 3/4\"/>



2 DELTA-WYE TRANSFORMER SCHEMATIC
NOT TO SCALE



5 ELECTRICAL GROUNDING REQUIREMENTS
NOT TO SCALE





1 CONDUIT PENETRATION DETAIL - EXTERIOR WALL
NOT TO SCALE



ARCHITECT	PBK Architects, Inc.
SAN ANTONIO	
601 N.W. Loop 410, Suite 400	
San Antonio, TX 78216	
210-820-0123 P	
210-829-5578 F	
TX Firm BR 1608	
ASSOCIATE ARCHITECT	B&A ARCHITECTS
210-820-0123 P	
210-829-5578 F	
TX Firm BR 1608	
ARCHITECT	LANDSCAPE
LUNY & FRANK ENGINEERING	
MECHANICAL	
ELECTRICAL	
PLUMBING	
HVAC	
TELECOMMUNICATIONS	
CONSTRUCTION	



WFAC Black Box Addition PKG 1
 1801 Main Luther King Dr.,
 San Antonio, TX 78203
 ISSUE FOR CONSTRUCTION



CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
06/14/2024	230462	
DRAWING HISTORY		
No.	Description	Date


ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

ELECTRICAL DETAILS


ISSUE FOR CONSTRUCTION

File Path: Autocad Doss:\Alamo CS_230462_Ar Philip College WBB Add#E23 WFAC - Blackbox Addition - A23.rvt
CHECKED BY: [Blank]
Checked
DRAWN BY: [Blank]
Author
Plot Stamp:
6/13/2024 12:24:06 PM

2 ISOLATED GROUND DETAIL NOT TO SCALE



3 GROUND WELL ASSEMBLY NOT TO SCALE



GENERAL NOTES

- CONDUCTOR SIZES SHOWN ARE MINIMUM AND MAY BE LARGER THAN THE MINIMUM SIZES REQUIRED BY NEC.
- INSTALL GROUNDING CONNECTIONS TO BUILDING STRUCTURE AND WATER PIPES AT LOCATIONS THAT ARE VISIBLE AND ACCESSIBLE FOR INSPECTION, MAINTENANCE, AND TESTING.
- INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC SERVICE ENTRANCE CONDUIT. BOND TO GROUND BUS USING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE.
- INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC FEEDER CONDUIT. BOND TO GROUND BUS USING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.122 USING THE FEEDER CIRCUIT OVERCURRENT DEVICE SIZE OR THE SEPARATELY DERIVED SYSTEM OVERCURRENT DEVICE SIZE.
- BOND HOT AND COLD WATER PIPING SYSTEMS.

KEYED NOTES


- INSTALL GROUND (NEUTRAL) CONDUCTOR SAME SIZE AS THE LARGEST PHASE CONDUCTOR IF THE LINE-TO-NEUTRAL LOAD EXCEEDS 5% OF THE CONNECTED LOAD. IF NEUTRAL LOAD IS SMALLER, INSTALL THE NEC MINIMUM GROUNDING CONDUCTOR.
- INSTALL GROUNDING ELECTRODE CONDUCTOR, SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE PHASE CONDUCTOR SIZE, BUT NOT SMALLER THAN 2 AWG UNLESS NOTED OTHERWISE.
- INSTALL EQUIPMENT GROUNDING CONDUCTOR SIZED BASED ON NEC TABLE 250.122 USING THE FEEDER OVERCURRENT DEVICE SIZE.
- BOND TO GAS PIPE ON THE BUILDING SIDE OF THE GAS METER.
- INSTALL GROUNDING ELECTRODE CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR SIZE.
- INSTALL A CONCRETE-ENCASED MAIN GROUNDING ELECTRODE IN THE BUILDING FOUNDATION AROUND THE ENTIRE PERIMETER OF THE BUILDING. LOCATE ELECTRODE IN THE BOTTOM ONE-THIRD OF THE FOUNDATION WITH AT LEAST 3 INCHES OF CONCRETE COVER. USE EITHER OF THE FOLLOWING MATERIALS FOR THE ELECTRODE:

BARE COPPER CABLE NOT SMALLER THAN THE GROUNDING ELECTRODE CONDUCTOR REQUIRED BY THE NEC AND NOT SMALLER THAN 2 AWG. REFER SPEC 28 05 26.

BARE OR GALVANIZED REBARS THAT ARE MADE ELECTRICALLY CONTINUOUS USING COPPER JUMPERS NOT SMALLER THAN THE NEC REQUIRED GROUNDING ELECTRODE CONDUCTOR AND NOT SMALLER THAN 4 AWG. USE REINFORCING BARS NOT SMALLER THAN THE FOLLOWING BASED ON THE TOTAL LENGTH OF THE INTERCONNECTED AND PARALLELED REBARS:

TOTAL LENGTH	MINIMUM REBAR SIZE
112 FT	1 3/8" (#1 BAR)
150 FT	1" (#6 BAR)
192 FT	3/4" (#6 BAR)
223 FT	5/8" (#6 BAR)
268 FT	1/2" (#4 BAR)
- BOND PERIMETER STRUCTURAL STEEL COLUMNS TO THE CONCRETE-ENCASED MAIN GROUNDING ELECTRODE. USE CANNULD CONNECTION TO ATTACH GROUNDING ELECTRODE CONDUCTOR TO BASE OF STEEL COLUMN. REFER SPEC 28 05 26.
- INSTALL A 'MAIN GROUND ELECTRODE GROUND BAR' FOR SINGLE POINT GROUNDING. LOCATE AT AN ACCESSIBLE AND VISIBLE POINT NEAR THE SERVICE ENTRANCE EQUIPMENT. MAKE CONNECTIONS TO THE GROUND BAR USING TWO-HOLE COMPRESSION SPADE LUGS THAT MEET IEEE 837 REQUIREMENTS. LABEL EACH CONNECTION TO THE GROUND BAR.
- LIGHTNING PROTECTION GROUNDING COUNTERPOISE - 3/0 AWG COPPER (IF LIGHTING PROTECTION SYSTEM IS SPECIFIED IN PROJECT, RE: SECTION 26 41 00).
- IF LIGHTNING PROTECTION SYSTEM IS SPECIFIED IN PROJECT (26 41 00), BOND THE LIGHTNING PROTECTION SYSTEM GROUNDING COUNTERPOISE TO THE MAIN GROUND ELECTRODE GROUND BAR. USE 4/0 AWG COPPER CABLE WITH 600 VOLT INSULATION. AT THE UNDERGROUND CONNECTION USE A COMPRESSION CONNECTOR THAT MEETS IEEE 837 REQUIREMENTS OR USE AN EXOTHERMIC WELD.
- USE THE 'MAIN GROUNDING ELECTRODE GROUND BAR' INSTEAD OF BUILDING STRUCTURAL STEEL IF THE FIRST OVERCURRENT DEVICE FOR THE SEPARATELY DERIVED SYSTEM IS WITHIN 50 FEET OF THE 'MAIN GROUNDING ELECTRODE GROUND BAR'.
- IF THE BUILDING STRUCTURE IS NOT STRUCTURAL STEEL, INSTALL 'MAIN GROUNDING ELECTRODE GROUND BAR EXTENSIONS' AT AN ACCESSIBLE AND VISIBLE LOCATION ADJACENT TO SEPARATELY DERIVED SYSTEMS THAT ARE MORE THAN 50 FEET FROM THE MAIN GROUNDING ELECTRODE GROUND BAR.
- INSTALL A COPPER GROUNDING BAR IN EACH TELECOMMUNICATIONS ROOM. CONNECT TO THE 'MAIN GROUNDING ELECTRODE GROUND BAR' USING 600V INSULATED 4/0 AWG COPPER CABLE AND COMPRESSION SPADE LUGS.
- INSTALL GROUND (NEUTRAL) CONDUCTOR THAT IS NOT LESS THAN THE PHASE CONDUCTOR AMPACITY. IF HIGH-HARMONICS ARE PRESENT MAKE NEUTRAL AMPACITY 200% OF THE PHASE CONDUCTOR.
- INSTALL BONDING CONDUCTOR THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE SERVICE OR SEPARATELY-DERIVED SYSTEM PHASE CONDUCTOR SIZE.
- INSTALL IRREVERSIBLE COMPRESSION CONNECTOR WITH TAMPER - PROOF HARDWARE OR INSTALL EXOTHERMIC WELD. REFER SPEC 28 05 26.
- BOND TO METAL PIPING SYSTEMS IN THE AREA SERVED BY THE SEPARATELY DERIVED SYSTEM.
- INSTALL BONDING JUMPER THAT IS SIZED BASED ON NEC TABLE 250.66 USING THE LARGEST SERVICE OR SEPARATELY DERIVED SYSTEM PHASE CONDUCTOR.
- BOND TO INCOMING WATER MAIN USING EXOTHERMIC WELD PROCESS OR OTHER APPROVED MECHANICAL BONDING PROCESS. REFER SPEC 28 05 26.
- TYPICAL EXOTHERMIC WELD PROCESS OR OTHER APPROVED MECHANICAL BONDING PROCESS. REFER SPEC 28 05 26, UNLESS NOTED OTHERWISE.



1 GROUNDING CONNECTION DETAIL SCALE: NOT TO SCALE



ARCHITECT: SAN ANTONIO PBK Architects, Inc.
601 N.W. Loop 410, Suite 400
San Antonio, TX 78216
210-820-0123 P
210-829-9578 F
TX Firm BR 1608
P&C.com



WFAC Black Box Addition PKG 1




CLIENT		Alamo Colleges
DATE	PROJECT NUMBER	230462
06/14/2024		
DRAWING HISTORY		
No.	Description	Date

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

ELECTRICAL DETAILS

E-603

ISSUE FOR CONSTRUCTION



SITE PLAN GENERAL NOTES:

1. COORDINATE ROUTING FOR ALL UNDERGROUND ELECTRICAL BRANCH CIRCUITS AND FEEDERS WITH OTHER DISCIPLINES PRIOR TO TRENCHING.
2. UNLESS NOTED OTHERWISE ALL UNDERGROUND CONDUIT SHOWN ON THIS PLAN TO BE MINIMUM 1" IN SIZE.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING UTILITIES CAUSED BY INSTALLATION OF NEW WORK.

SITE PLAN KEYED NOTES:



- 1 EXISTING ELECTRICAL MANHOLE.
- 2 NEW UNDERGROUND EASEMENT FOR NEW PRIMARY POWER FOR UTILITY TRANSFORMER. FIELD VERIFY THAT SPARE CAPACITY IS AVAILABLE.
- 3 NEW 480277V 750KVA TRANSFORMER SHALL BE PROVIDED FROM ALAMO COLLEGES. CONTRACTOR SHALL COORDINATE EXACT LOCATION WITH ARCHITECTURAL PLANS PROVIDE (1) 1 1/2" CONDUIT FOR POWER.
- 4 NEW UNDERGROUND ROUTE FOR SECONDARY TO MAIN SERVICE DISCONNECT. PROVIDE (2) 3" CONDUITS FOR POWER.
- 5 NEW 480277V, 40 KW CUMMINS MODEL NUMBER: C40 N6 FOR FIRE PUMP.
- 6 NEW UNDERGROUND PATHWAY FROM GENERATOR TO 2ND FLOOR ATS IN MEZZAINE.
- 7 REROUTED PATHWAY FOR EXISTING UNDERGROUND DUCKSANK WITH 4 EXISTING CONDUITS. CONTRACTOR SHALL VERIFY EXACT PATHWAY OF EXISTING CONDUITS AND FEEDERS SIZES WITHIN EXISTING MANHOLES. CONTRACTOR SHALL COORDINATE NEW PATHWAY WITH ST. PHILLIPS UTILITY FACILITIES TO ENSURE PATHWAY CAN BE Routed.
- 8 RELOCATED CONDENSING UNIT AND ASSOCIATED DISCONNECT. COORDINATE WITH MECHANICAL FOR EXACT LOCATION.
- 9 EXISTING DISTRIBUTION MAIN SERVICE DISCONNECT DP-6 FOR ADJACENT WATSON FINE ARTS BUILDING.
- 10 EXISTING UTILITY TRANSFORMER FOR WATSON FINE ARTS.
- 11 PROPOSED NEW PATHWAY FOR RELOCATED EXISTING CONDUITS FROM DP-6. CONTRACTOR SHALL VERIFY WHERE CONDUITS ARE FED TO.
- 12 NEW LOCATION OF PEDESTRIAN POLES. COORDINATE EXACT LOCATION WITH ARCHITECTURAL DRAWINGS. UTILIZE EXISTING CIRCUIT IF AVAILABLE. IF CIRCUIT ISNT OBTAINABLE CONTRACTOR SHALL UTILIZE NEAREST AVAILABLE SPARE IN PANEL WITH IDENTICAL VOL TAG.



ARCHITECT	PBK Architects, Inc. SAN ANTONIO 601 N.W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm BR 1608
ASSOCIATE ARCHITECT	B&A ARCHITECTS 1100 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-441-9922
LANDSCAPE ARCHITECT	LANDSCAPE 1111 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-441-9922
MECHANICAL ENGINEER	LUNY & FRANK ENGINEERING 1111 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-441-9922
ELECTRICAL ENGINEER	MEYER PROFESSIONALS 1111 N. LOOP WEST SUITE 1000 SAN ANTONIO, TX 78207 210-441-9922



WFAC Black Box Addition PKG 1



CLIENT	Alamo Colleges	
DATE	06/14/2024	
PROJECT NUMBER	230462	
DRAWING HISTORY		
No.	Description	Date



ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1

SITE POWER PLAN

1 SITE POWER PLAN
SCALE: 1" = 20'-0"

KEYNOTES




- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P5 2" VENT UP AND 3" WASTE DOWN.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P8 2" WASTE PIPING DOWN FROM SHOWER DRAIN ABOVE.
- P9 3" WASTE PIPING DOWN FROM FLOOR DRAIN ABOVE.
- P10 4" WASTE PIPING DOWN FROM FLOOR SINK ABOVE.
- P11 4" WASTE DOWN FROM WATER CLOSET ABOVE.
- P12 4" WASTE PIPING DOWN FROM FLOOR CLEAN OUT ABOVE.
- P13 2" WASTE DOWN FROM LAV/SINK ABOVE.
- P14 4" WASTE DOWN FROM WCO ABOVE.
- P17 3" WASTE DOWN FROM MOP SINK.
- P18 2" WASTE DOWN FROM URINAL.
- P20 2" WASTE DOWN FROM WASHING MACHINE BOX.
- P21 2" WASTE DOWN FROM DRINKING FOUNTAIN.
- P28 SANITARY SEWER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P29 STORM WATER PIPING STUB-OUT. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P34 REFER TO SPECIFICATIONS FOR ESP-1
- P109 FORCED MAIN FROM SUMP PUMP IN CRAWL SPACE.
- P110 SUMP PUMP DISCHARGE CONNECT TO GRATE INLET. REFER TO CIVIL DWGS. FOR CONTINUATION.
- P111 PROVIDE DUPLEX SUMP PUMP MODEL EQUAL TO STANCOR SEW-150 200/3PH 100 GPM @ 20' OF HEAD.
- P112 ELEVATOR DISCHARGE PIPING UP TO OIL SEPARATOR.
- P113 2" FORCED MAIN TO OIL SEPARATOR.
- P115 ELEVATOR SUMP PUMP ESP-1. PUMP TO BE EQUAL TO LIBERTY PUMP 280 50 GPM, 14' HEAD, 1-1/2" DISCHARGE 1/2HP, 115V/1PH.



ARCHITECT PBK Architects, Inc.
 SAN ANTONIO
 601 N. W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P
 210-829-0578 F
 TX Firm BR 1659
 ASSOCIATE ARCHITECT
 DONALD C. RICHARDS
 6152
 07/08/2024
 LEAF ENGINEERS
 F-18672



WFAC Black Box Addition PKG 1
 1801 Main, Luther King Dr.,
 San Antonio, TX, 78203
 90%CD - IFR




CLIENT		
Alamo Colleges		
DATE	PROJECT NUMBER	
07/08/2024	230462	
DRAWING HISTORY		
No.	Description	Date
1	CITY COMMENTS	06/05/2024
2	CITY COMMENTS	06/12/2024
3	CITY COMMENTS	06/24/2024
4	CITY COMMENTS	07/08/2024

90%CD - IFR
 BUILDING NUMBER 1


CRAWLSPACE PLUMBING PLAN

PU-101-A

File Path: Autocad Docs://Name CS_230462_Al Philip College WBB AddP23 WFAC - Blackbox Addition - A03.rvt
 CHECKED BY: Checker
 DRAWN BY: Author
 Plot Stamp: 7/8/2024 7:29:33 AM



1 1ST LEVEL ENLARGED PLUMBING PLAN - AREA C
SCALE: 1/4" = 1'-0"



2 1ST LEVEL ENLARGED PLUMBING PLAN - AREA D
SCALE: 1/4" = 1'-0"

KEYNOTES

- P3 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P6 2" VENT UP AND 4" WASTE DOWN.
- P10 4" WASTE PIPING DOWN FROM FLOOR ABOVE.
- P39 ROOF DRAIN PIPING DOWN TO BELOW FLOOR. SIZE AS NOTED.
- P45 3/4" COLD WATER, 3/4" HOT WATER DOWN AND 2" VENT UP.
- P46 3/4" COLD WATER DOWN AND 2" VENT UP.
- P48 3/4" COLD WATER AND 3/4" HOT WATER DOWN TO SHOWER VALVE.
- P49 1 1/4" COLD WATER DOWN AND 2" VENT UP.
- P71 HOT WATER DOWN IN CHASE / WALL SIZE AS NOTED.
- P73 PROVIDE BALANCING VALVE.
- P114 PROVIDE ELEVATOR SLUMP SYSTEM EQUAL TO PARK ELYC-100 SEPARATOR MODEL ESC-100 50 GPM FLOW RATE 100 GALLON CAPACITY.






ARCHITECT	PBK Architects, Inc.
SAN ANTONIO 601 N. W. Loop 410, Suite 400 San Antonio, TX 78216 210-829-0123 P 210-829-0578 F TX Firm SR 1659	
ASSOCIATE ARCHITECT	173.05.184
REGISTERED ARCHITECT	173.05.184
REGISTERED ENGINEER	173.05.184
REGISTERED ELECTRICAL ENGINEER	173.05.184
REGISTERED MECHANICAL ENGINEER	173.05.184
REGISTERED PLUMBING ENGINEER	173.05.184
REGISTERED CIVIL ENGINEER	173.05.184
REGISTERED SURVEYOR	173.05.184
REGISTERED PROFESSIONAL	173.05.184
REGISTERED WATER ENGINEER	173.05.184
REGISTERED WASTE ENGINEER	173.05.184



WFAC Black Box Addition PKG 1


1801 Main, Luber King Dr.,
San Antonio, TX 78203
90%CD - IFR




CLIENT		Alamo Colleges
DATE	07/08/2024	PROJECT NUMBER
DRAWING HISTORY		230462
No.	Description	Date
1	CITY COMMENTS	07/08/2024
90%CD - IFR		
BUILDING NUMBER	1	

PLUMBING ENLARGED PLAN


P-401




10 COMPRESSED AIR OUTLET DETAIL
SCALE: NOT TO SCALE



7 EMERGENCY SHOWER/EYEWASH DETAIL
SCALE: NOT TO SCALE




4 ELECTRIC WATER HEATER PIPING
SCALE: N.T.S




1 ADJUSTABLE CLEVIS PIPE HANGER DETAIL
SCALE: NOT TO SCALE


NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"




11 WALL HYDRANT DETAIL
SCALE: NOT TO SCALE



8 SHOCK ARRESTOR DETAIL
SCALE: NOT TO SCALE




5 WASHER / DRAIN BOX CONNECTION DETAIL
SCALE: NOT TO SCALE




2 ADJUSTABLE ROLLER PIPE HANGER DETAIL
SCALE: NOT TO SCALE


NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"




12 WALL HYDRANT DETAIL
SCALE: NOT TO SCALE



9 AIR COMPRESSOR PIPING DETAIL
SCALE: NOT TO SCALE



6 BACKFLOW PREVENTER MOUNTING DETAIL
SCALE: NOT TO SCALE



3 TRAPEZOID PIPE HANGER DETAIL
SCALE: NOT TO SCALE

NOM. SIZE	3/4"	1"	1 1/4"	1 1/2"	2"	3"	4"	5"	6"	8"	10"	12"	14"	16"	18"	20"	24"
PIPING	7"	7"	7"	9"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"	10"
TUBING	5"	6"	6"	6"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"	8"





ARCHITECT	PBK Architects, Inc.
SAN ANTONIO	601 N.W. Loop 410, Suite 400
San Antonio, TX 78216	210-820-0123 P
	210-829-0578 F
	TX Firm BR 1606
ASSOCIATE ARCHITECT	MAX ARCHITECTS
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE
DESIGNER	LANDSCAPE



WFAC Black Box Addition PKG 1

1801 Melvin Luther King Dr.,
San Antonio, TX 78203


ISSUE FOR CONSTRUCTION




CLIENT		PROJECT NUMBER	
Alamo Colleges		230462	
DATE	06/14/2024		
DRAWING HISTORY			
No.	Description	Date	

ISSUE FOR CONSTRUCTION
BUILDING NUMBER 1


PLUMBING DETAILS




4 ELEVATOR OIL INTERCEPTOR SUMP PIT DETAIL
SCALE: NOT TO SCALE



1 DOMESTIC COLD WATER ENTRY
SCALE: N.T.S.




2 FIRE PUMP
SCALE: N.T.S.



3 DUPLIX PACKAGE PUMPING SYSTEM
SCALE: N.T.S.



ISSUE FOR CONSTRUCTION



1 SITE TECHNOLOGY PLAN
SCALE: 1" = 30'-0"

TECHNOLOGY KEYNOTES


- TS1 INDICATES THE APPROXIMATE LOCATION OF THE NEW BUILDING IDF. CONDUITS SHALL BE STUB EVENTLY AT +8 A.F.F TO ENTER THE NEW MDF/IDF
- TS3 CONTRACTOR TO INSTALL TWO (2) FOUR INCH (4") CONDUIT WITH A PULLING LINE FROM THIS MANHOLE ALL THE WAY TO THE NEW IDF ROUTED AT 4 B.F.G. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT. THE UNDERGROUND CONDUIT PATHWAY WILL BE INSTALLED BY THE DIV 26 CONTRACTOR.
- TS4 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING MANHOLE
- TS5 INDICATES THE APPROXIMATE LOCATION OF AN EXISTING CONDUIT PATHWAY TO BE REMOVED CONTRACTOR SHALL PULL BACK EXISTING FIBER FROM THE EXISTING MANHOLE ALL THE WAY BACK TO THE PREVIOUS BOX. FIBER TO BE RE-USED IF POSSIBLE. CONTRACTOR WILL RE-ROUTE THE EXISTING FIBER AND FUSE SPLICED AT THE SAME BOX IT WAS PULLED FROM THE BEGINNING JUST FROM A DIFFERENT PATHWAY. CONTRACTOR SHALL PAY FOR ANY DAMAGE TO EXISTING FIBER.
- TS6 INDICATES THE APPROXIMATE LOCATION FOR THE NEW PATHWAY FOR THE EXISTING FIBER TO BE RE-ROUTED TO MAINTAIN THE SERVICE UP AND RUNNING. CONTRACTOR TO FIELD VERIFY THE AMOUNT OF CONDUIT NEEDED FOR THIS NEW ROUTE TO WORK AS THE PREVIOUS.
- TS8 INDICATES THE APPROXIMATE LOCATION OF THE EXISTING CAMPUS MDF. CONDUITS SHALL BE STUBBED EVENTLY AT +8 A.F.F TO ENTER THE MDF/IDF.
- TS9 CONTRACTOR TO PULL A NEW ONE (1) 24-STRAND SINGLE MODE FIBER OUTDOOR/ARMORED-RATED FROM THE EXISTING CAMPUS MDF INTO THE NEW BLACK BOX BUILDING IDF. PROVIDE TWO (2) 3-CELL MAXCELL INNERDUCT IN EACH CONDUIT.
- TS10 CONTRACTOR TO FIELD VERIFY THE EXISTING PATHWAY AND REROUTE THE EXISTING FIBER INTO THE NEW PATHWAY PRIOR TO ANY CONSTRUCTION TO MAINTAIN THE NETWORK ALIVE. CONTRACTOR TO LABEL ALL SPOOLS IN THE MANHOLE ACCORDING TO ACC STANDARDS AND REMOVED ANY NON-WORKING CABLES ALL THE WAY TO THE CAMPUS MDF PATHWAY.
- TS11 CONTRACTOR TO REMOVE ALL NON-WORKING LOW VOLTAGE CABLE ALL THE WAY TO THE CAMPUS MDF DURING THE NEW FIBER PULLING FOR THIS PROJECT.





ARCHITECT **PBK Architects, Inc.**
 SAN ANTONIO
 601 N.W. Loop 410, Suite 400
 San Antonio, TX 78216
 210-829-0123 P.
 210-829-0578 F.
 TX Firm BR 1608


ASSOCIATE ARCHITECT **B&A ARCHITECTS**
 210-829-0123 P.
 210-829-0578 F.
 TX Firm BR 1608

LANDSCAPE ARCHITECT **LEAF ENGINEERS**
 1801 Mainfr Luther King Dr.,
 San Antonio, TX 78203
 TX Firm BR 1608





KEY PLAN
NORTH PLAN TRUE



2024/06/14
 LEAF ENGINEERS
 E-18612

CLIENT		
DATE	PROJECT NUMBER	
2024/06/14	230462	
DRAWING HISTORY		
No.	Description	Date
ISSUE FOR CONSTRUCTION		
BUILDING NUMBER		1

SITE TECHNOLOGY PLAN

TS-101